

FREEBOARD PARTICULARS

Name:-

Yard No:- 148-149-150.

Registered Length 406'35

" Breadth 56'05 9.56"

" Depth 26'9 26.92

Tonnage U.D. 4800 approx. Gross 5170 approx.

Length on Load Line 405'0"

Depth moulded 29'5" upper Dk. 8'6" Shelter Lwr. dks.

Camber of Deck 1'1 1/2

Length of Beam 55'9"

Rule thickness of wood deck

Sheer at side at stem 7'0"

" " " " stern 3'10 1/2

" " 1/8 len. from stem 3'3"

" " 1/8 " " stern 1'8"

Lowest point of sheer is amidships.

Length of forecastle actual on deck 32'6" Height 7'6"

Overhang of forecastle deck shaft bulkhead -

Length of bridge - Height -

Overhang of bridge deck - Front - Aft end -

Length of Luggage Well 5'3"

" " " Hatch 5'3" x 20'0"

Overhang of poop beyond bulkhead -

Bulkhead at fore end of bridge -

" " aft " " forecastle To Rule

Stiffening to bridge front bulkhead -

" " bulkhead at fore end of poop -

Size and number of freeing ports Open Rails

Height of hatch coamings above deck 2'8" SHUTTER COVERS 3" W.W.

Size of hatches nos. 1, 27'0" x 20'0". nos. 2, 3, 4, & 5, 28'10 1/2" x 20'0"

Cuppers To Rule

Height of lowest side scuttle above base 38'6"

Dead displacement 13,200 tons on 25'9" BK.

ons per inch at same 47.0

Depth of keel below base line 25'8"



© 2020

Lloyd's Register
Foundation

003458-003462-0140