

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

NOV 13 1937

Received at London Office

Date of writing Report 5th Nov, 1937 When handed in at Local Office 12 NOV. 1937 Port of Sunderland
 No. in Survey held at Sunderland Date, First Survey 16th August Last Survey 9th November 1937
 Reg. Book. 24611 on the M.V. "ETTRICKBANK" (Number of Visits 17)

Tons { Gross 5138
 Net 3040

Built at Sunderland By whom built W. Duxford & Sons Ltd. Yard No. 637 When built 1937
 Owners Merch Transport & Trading Co. Ltd. Port belonging to Glasgow
 Electric Light Installation fitted by The Sunderland Eng & Ing. Co. Ltd. Contract No. 637 When fitted 1937
 Is the Vessel fitted for carrying Petroleum in bulk No

System of Distribution Double wire ✓

Pressure of supply for Lighting 110 ✓ volts, Heating — volts, Power 110 ✓ volts.

Direct or Alternating Current, Lighting Direct ✓ Power Direct ✓

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes ✓

Generators, do they comply with the requirements regarding temperature rise Yes ✓, are they compound wound Yes ✓
 are they over compounded 5 per cent. Yes ✓, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel No ✓, is an adjustable regulating resistance fitted in series with each shunt field Yes ✓

Have certificates of test results for machines under 100 kw. been submitted and approved Yes, Certs. herewith ✓ Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing —

Are all terminals accessible, clearly marked, and furnished with sockets Yes ✓, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes ✓

Are the lubricating arrangements of the generators as per Rule Yes ✓

Position of Generators Engine room starboard side ✓, is the ventilation in way of the generators satisfactory Yes ✓ are they clear of all inflammable material Yes ✓ if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —

are the generators protected from mechanical injury and damage from water, steam or oil Yes ✓, are their axes of rotation fore and aft Yes ✓

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes ✓ are the prime movers and their respective generators in metallic contact Yes ✓ Main Switch Boards, where placed Engine room starboard side ✓

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes ✓, are they protected from mechanical injury and damage from water, steam or oil Yes ✓, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —, are they constructed wholly of durable, non-ignitable non-absorbent materials Yes ✓

is all insulation of high dielectric strength and of permanently high insulation resistance —, is it of an approved type —, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework Yes ✓, is the non-hygroscopic insulating material of an approved type Yes ✓

and is the frame effectively earthed Yes ✓ Are the fittings as per Rule regarding:— spacing or shielding of live parts Yes ✓, accessibility of all parts Yes ✓, absence of fuses on back of board Yes ✓, temperature rise of omnibus bars Yes ✓, individual fuses to voltmeter, pilot or earth lamp Yes ✓, are moving parts of switches alive in the "off" position No ✓

are all screws and nuts securing connections effectively locked Yes ✓ are any fuses fitted on the live side of switches No ✓

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Are turbine driven generators fitted with emergency trip switch as per rule — Are cupboards or compartments containing switchboards composed of fire-resisting material or lined with approved material — Instruments on main switchboard 2 ✓ ammeters 2 ✓

voltmeters — synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection —

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system E lamps coupled to E through switches of fuses ✓

do these comply with the requirements of the Rules Yes ✓ are the fusible cutouts of an approved type Yes ✓ have the reversed —



current protection devices been tested under working conditions — **Joint Boxes, Section and Distribution Boards,** is the

construction, protection, insulation, material, and position of these as per rule *yes*

Cables: Single, twin, concentric, or multicore *Single twin* are the cables insulated and protected as per Tables IV, V, X or XI of the Rules *yes*

If the cables are insulated otherwise than as per Rule, are they of an approved type — **Fall of Pressure,** state maximum between bus bars and

any point of the installation under maximum load *3.5 volts* **Cable Sockets,** are the ends of all cables having a sectional

area of 0.04 square inch and above provided with soldering sockets *yes* **Paper Insulated and Varnished Cambric Insulated Cables,**

If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with

insulating compound — or waterproof insulating tape *yes* **Cable Runs,** are the cables fixed as far as possible in accessible positions

not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical

damage *yes* Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit *yes*

Support and Protection of Cables, state how the cables are supported and protected *L.C.A. & B. Cables clipped up in engine*

room & 'twendesk; L.C. & B. cables clipped up in accommodation

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in

separate grooves — If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *yes*

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements —

Joints in Cables, state if any, and how made, insulated, and protected *none made*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands

yes **Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the

holes efficiently bushed *yes* state the material of which the bushes are made *Lead & fibre*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas —

are their connections made as per Rule *yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes* **Emergency Supply,** state

position and method of control of the emergency supply and how the generator is driven —

Navigation Lamps, are these separately-wired *yes*, controlled by separate switch and separate fuses *yes*, are the fuses double pole *yes*,

are the switches and fuses grouped in a position accessible only to the officers on watch *yes*

has each navigation lamp an automatic indicator as per Rule *yes* **Secondary Batteries,** are they constructed and fitted as per Rule —

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected —

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected —

how are the cables led —

where are the controlling switches situated —

are all fittings suitably ventilated *yes*, are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials *yes*

Heating and Cooking Appliances, are they constructed and fitted as per Rule —, are air heaters constructed and fitted as per Rule —

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —

Motors, are their working parts readily accessible *yes*, are the coils self-contained and readily removable for replacement *yes*,

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes*, are the motors placed in well-ventilated compartments in which

inflammable gases cannot accumulate and clear of all inflammable material *yes*, are they protected from mechanical injury and damage from

water, steam or oil *yes*, are their axes of rotation fore and aft *yes*, if situated near unprotected woodwork or other combustible

material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —

if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —

have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing — **Control Gear and Resistances,** are the generator

field and motor speed regulators, starters and controllers constructed and fitted as per Rule *yes* **Lightning Conductors,** where lightning conductors

are required, are these fitted as per Rule — **Ships carrying Oil having a Flash Point less than 150 F.** Have the special requirements of

the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and

fittings — are all fuses of the fitted cartridge type — are they of an approved type —

If portable lamps for use in damp or spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office —

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule *yes*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	2	20	110	182	685	Single cylinder		
AUXILIARY						steam engine		
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	Circuit.	Rule.			
MAIN GENERATOR	1	.12	37	.064	182	189	69	V.C.	L.C. & B.
SHORE CONNECTIONS	1	.2	37	.083		266	80	V.C.	L.C. & B.
AUXILIARY GENERATOR									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER									
MOTOR									
ENGINE ROOM	1	.007	7	.036	21.2	24	72	V.I.R.	L.C. & B. in pipe
BOILER ROOM	1	.045	7	.064	77.23	92	216	V.I.R.	L.C. & B.
AUXILIARY SWITCHBOARD	1	.003	1	.064	12.75	12.9	40	V.I.R.	L.C. & B.
Supp. Engrs' Accom.	1	.01	7	.044	26.28	31	256	V.I.R.	L.C. & B.
Mainmast D.B.	1	.01	7	.044	21.2	31	256	V.I.R.	L.C. & B.
Forward D.B.	1	.003	1	.064	10	12.9	40	V.I.R.	L.C. & B.
Saloon D.B.	1	.003	3	.036	7	12	112	V.I.R.	L.C. & B.
Sally Pass 2@	1	.007	7	.036	11.6	24	192	V.I.R.	L.C. & B. & L.C. & B.
Accommodation									
Trav. & Capt's Accom.	1	.007	7	.036	11.6	24	192	V.I.R.	L.C. & B. & L.C. & B.
WIRELESS	1	.007	7	.036	15	24	192	V.I.R.	L.C. & B.
SEARCHLIGHT	1	.0015	1	.044	.36	6.1	320	V.I.R.	L.C. & B.
MASTHEAD LIGHT	1	.0015	1	.044	.36	6.1	56	V.I.R.	L.C. & B.
SIDE LIGHTS	1	.0015	1	.044	.14	6.1	30	V.I.R.	L.C. & B.
COMPASS LIGHTS	1	.0015	1	.044	.36	6.1	608	V.I.R.	L.C. & B.
STERN LIGHTS	1	.0017	40	.0076	2.18	5.0	120	V.I.R.	Cat tape
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP										
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR	1	1	.0045	7	.029	16	18.2	76	V.I.R.	L.C. & B.
VENTILATING FANS										
Oil burning fan	1	1	.0045	7	.029	12	18.2	90	V.I.R.	L.C. & B.
Crane motor	1	1	.0045	7	.029	16	18.2	60	V.I.R.	L.C. & B.
Priming Pump	1	1	.003	1	.064	8	12.9	110	V.I.R.	L.C. & B.
Refrigerator	1	1	.007	7	.036	24	24	70	V.I.R.	L.C. & B.
Refrig. Pump	1	1	.0015	1	.044	6	6.1	80	V.I.R.	L.C. & B.
Oil separators 3@	1	1	.007	7	.036	24	24	120	V.I.R.	L.C. & B.

All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

16th Sunderland Forge & Eng Co Ltd. Electrical Engineers. Date 10 - 11 - 1937
A. S. Gurney

COMPASSES.

Distance between electric generators or motors and standard compass 90 feet

Distance between electric generators or motors and steering compass 80 feet

The nearest cables to the compasses are as follows:—

A cable carrying 14 Ampères on the feet from standard compass 10 feet from steering compass.

A cable carrying 14 Ampères 10 feet from standard compass on the feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power? *yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted? *yes*

The maximum deviation due to electric currents was found to be *nil* degrees on *every* course in the case of the standard compass, and *nil* degrees on *every* course in the case of the steering compass.

WILLIAM DOXFORD & SONS, Limited.
R. Maxwell
Builder's Signature. Date

Is this installation a duplicate of a previous case? *yes* If so, state name of vessel *H. V. " Eskbank "*

General Remarks (State quality of workmanship, opinions as to class, &c.) *The above installation has been fitted out under special survey. The materials used and the workmanship are good. On completion the dynamo, governors, main board, switches, fuses, cables, motors and fittings were examined and tested under working conditions and found satisfactory and suitable for a classed vessel. The insulation resistance was tested and found good. This vessel is fitted with Wireless Direction Finding apparatus and Echo sounding device.*

Notes

L.Y.

16/11/37.

Total Capacity of Generators 40 Kilowatts.

The amount of Fee ... £ 25 : - : When applied for, 12 NOV 1937

Travelling Expenses (if any) £ : : When received, 13-11-37 15/11

G. Antusson
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

FRI 19 NOV 1937

Assigned

See Old JE 32235



© 2020

Lloyd's Register Foundation

7509.36—Transfer.
The Surveys are requested not to write on or below the space for Committee's Minute.