

COPY.

Lloyd's Register of Shipping.



Port Oslo

16th August 1933

This is to Certify that

Per Björn-Röli

the undersigned Surveyor to this Society did at the request of

Hvalfangernes Assuranceforening, Sandefjord examine the steamer
"MAUDIE" 4818 tons gross of Tönsberg, whilst lying in Nylands
floating dock on the 9th June 1933 and subsequently to ascertain
and estimate damage stated to have been sustained by grounding on
the 17th January and 14th February 1933 at Harburg.

For further particulars see logbook.

On examination found:-

Recommend:-

On the starboard side:-

B strake no. 4 slightly
indented.

To be faired in place.

C " " 4 indented.

To be removed, faired and replaced.

D " " 3 slightly
indented.

To be faired in place.

2 floors and 1 side girder
bent.

To be faired.

On the port side:-

B strake no. 4 slightly
indented.

To be faired in place.

C " " 3 indented.

To be removed, faired and replaced.

D " " 4 slightly
indented.

To be faired in place.

C " " 5 slightly
indented.

To be faired in place.

1 floor bent.

To be faired in place.

The bilge keel stb. side
bent.

To be partly removed, faired and re-
placed. Kr. 3 080.-

No. 1 & 2 double bottom tanks
to be cleaned for access and
to be tested. " 2 000.-

To be forwarded.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for accuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Committee or any Member thereof, or Surveyors, or other Officers or Agents of the Society."

-II-

S/S "MAUDIE"

On examination found:

Recommend:-

Forwarded:-

Docking 4 days

Kr. 5 880.-

" 4 240.-

Kr. 10 120.-

The damage has been repaired as recommended.

Fee kr. 80.-

Perizon Røer



© 2020

Lloyd's Register
Foundation

01732/2