

16 AUG 1943

Rpt. C.11 (Comp.).

EMPIRE AIRMAN  
36724 Etc.

R.T. 0094

Index. No. 37360  
(For London Office only).

# Claydon's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

N<sup>o</sup> 33766

Ship's Name <b>M.V. EMPIRE INVENTOR</b>	Official Number <b>180053</b>	Nationality and Port of Registry <b>British Sunderland</b>	Gross Tonnage <b>9912</b>	Date of Build <b>1943.</b>	Port of Survey <b>Sunderland</b>
Moulded Dimensions: Length <b>476.125</b> Breadth <b>68.00</b> Depth <b>36.00</b>					Date of Survey <b>During Construction</b>
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>21467</b> tons					Surveyor's Signature <b>W. E. Lull</b>
Coefficient of fineness for use with Tables <b>76.758</b>					Particulars of Classification <b>+100 A.1. Carrying Petroleum in Bulk (Contemplated)</b>

<b>Depth for Freeboard (D).</b> Moulded depth ... <b>36.00</b> Stringer plate ... <b>82... .07</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ Depth for Freeboard (D) = <b>36.07</b>	<b>Depth correction.</b> (a) Where D is greater than Table depth (D - Table depth) R = $(36.07 - 31.74) 3 = +12.99$ $4.33$ (b) Where D is less than Table depth (if allowed) (Table depth - D) R = If restricted by superstructures	<b>Round of Beam correction.</b> Moulded Breadth (B) <b>68.00</b> Standard Round of Beam $= \frac{B \times 12}{50} = 16.32$ Ship's Round of Beam = <b>17</b> Difference <b>.68</b> Restricted to Correction $= \frac{\text{Diff}^*}{4} \times \left( 1 - \frac{S_1}{L} \right) = \frac{.68}{4} \times .7003 = -.12$
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...	<b>108.80</b>	<b>108.20</b>	<b>7.5</b>	✓	<b>108.20</b>
„ overhang ...					
R.Q.D. enclosed ...					
„ overhang ...					
Bridge enclosed ...					
„ overhang aft ...					
„ overhang forward					
F'cle enclosed ...	<b>34.5</b>	<b>34.50</b>	<b>7.5</b>	✓	<b>34.50</b>
„ overhang ...					
Trunk aft ...					
„ forward ...					
Tonnage opening aft ...					
„ „ forward					
Total ...	<b>142.70</b>	<b>142.70</b>			<b>142.70</b>

Standard Height of Superstructure **7.5"**  
 „ „ R.Q.D. ✓  
 Deduction for complete superstructure **42.00"**  
 Percentage covered  $\frac{S}{L} =$   
 $\frac{S_1}{L} =$   
 $\frac{E}{L} =$   
 Percentage from Table, Line A. Tanker **20.98**  
 (corrected for absence of forecastle (if required)) ✓  
 Percentage from Table, Line B. ✓  
 (corrected for absence of forecastle (if required)) ✓  
 Interpolation for bridge less than 2L (if required) ✓  
 Deduction = **42.00 × .2098 = -8.81"**

## SHEER CORRECTION.

Station	Standard Ordinate	S M	Product	Actual Ordinate	Effective Ordinate	S M	Product
A.P. ...	<b>57.61</b>	1	<b>57.61</b>	<b>45 3/4</b>	<b>45.75</b>	1	<b>45.75</b>
1/4 L from A.P. ...	<b>25.635</b>	4	<b>102.54</b>	<b>20 1/2</b>	<b>20.50</b>	4	<b>82.00</b>
1/2 L „ ...	<b>6.34</b>	2	<b>12.68</b>	<b>5 3/8</b>	<b>5.375</b>	2	<b>10.75</b>
Amidships ...	-	4	-	0	-	4	-
3/4 L from F.P. ...	<b>12.675</b>	2	<b>25.35</b>	<b>6 3/4</b>	<b>6.75</b>	2	<b>13.50</b>
3/4 L „ ...	<b>51.27</b>	4	<b>205.08</b>	<b>26 3/4</b>	<b>26.75</b>	4	<b>107.00</b>
F.P. ...	<b>115.23</b>	1	<b>115.23</b>	<b>62</b>	<b>62.00</b>	1	<b>62.00</b>
Total ...			<b>518.49</b>				<b>321.00</b>

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( \frac{75-S}{2L} \right) = \frac{197.49}{18} \left( \frac{75-1499}{6001} \right) = +6.58$   
 If limited on account of midship superstructure. ✓

Mean actual sheer aft =  
 Mean standard sheer aft =  
 Mean actual sheer forward =  
 Mean standard sheer forward =  
 Length of enclosed superstructure forward of amidships =  
 „ „ aft of „ = Nil

Deduction for Tropical Freeboard.  
 Addition for Winter and Winter North Atlantic Freeboard.

Depth to Freeboard Deck = **36.07**  
 Summer freeboard = **8.08**  
 Moulded draught (d) = **27.99**

Deduction for Tropical freeboard and addition for

Winter freeboard =  $\frac{d}{4}$  inches = **7"**Addition for Winter North Atlantic Freeboard (if required) = **7.0 + 4.76 = 11 3/4"**

Deduction for Fresh Water.

Displacement in salt water at summer load water line

 $\Delta = 19524$ 

Tons per inch immersion at summer load water line

 $T = 65.2$ Deduction =  $\frac{\Delta}{40T}$  inches**= 7.49****= 7 1/2"**

TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient  $\frac{.758 + .68}{1.36} = 1.438/1.36$ 

	+	-
Depth Correction ...	<b>12.99</b>	-
Deduction for superstructures ...	-	<b>8.81</b>
Sheer correction ...	<b>6.58</b>	-
Round of Beam correction ...	-	<b>.12</b>
Correction for Thickness of Deck amidships ...	-	-
Other corrections, scantlings, etc. ...	-	-
<b>19.57</b>	<b>3.93</b>	<b>+ 10.64</b>

Summer Freeboard = **97.05**

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:

Tropical Fresh Water Line above Centre of Disc ... **14 1/2"**  
 Fresh Water Line „ „ ... **7 1/2"**  
 Tropical Line „ „ ... **7"**  
 Winter Line below „ „ ... **7"**  
 Winter North Atlantic Line „ „ ... **11 3/4"**

Tropical Fresh Water Freeboard ... **8' 10 1/2"**  
 Fresh Water „ „ ... **7' 5 1/2"**  
 Tropical „ „ ... **7' 6"**  
 Winter „ „ ... **8' 8 3/4"**  
 Winter North Atlantic „ „ ... **11' 4 1/4"**



A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

Displacement at 28'3" draft = 19547 tons.

Long Per Inch = 65.2.

Equi. length of poop:

$$\begin{array}{r} 103.79 + \frac{1}{3} \times 6.62 \\ 4.41 \\ \hline 108.20 \end{array}$$

Trade of ship

Names of sister ships *M.V. Empire Alliance Std. Rpt. No. 33692*

Builder's name and yard number *Messrs. Sir James Laing & Son Ltd. Yard No. 749.*

Owners *Ministry of War Transport.*

Fee £ 20

*Will be changed on F.E. Report.*



© 2020

Lloyd's Register  
Foundation