

(LLOYD'S REGISTER.)

G.R. 130
Lloyd's Register. 1924

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) K. Q. W. L.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
147,680..	Taunton.	152 in 1924 London.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Stockton-on-Tees	1924	Craig, Taylor & Co. Stockton-on-Tees
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	244	Feet.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	244	Tenths
Rigged ...	Schooner	Main breadth to outside of plank ...	36	7
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	15	8.5
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	22	4
Galleries ...	None	Depth from top of beam amidships to top of keel ...	21	8
Head ...	None	Round of beam ...	38	7.5
Framework and description of vessel ...	Steel Cargo	Length of engine room, if any ...	38	--
Number of Bulkheads ...	Four			
Number of water ballast tanks, and their capacity in tons ...	Seven- 633 Tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 3305 Tons. Ditto per inch immersion at same depth } 18.2 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Tri-Compound Inverted Cylinders	Engines. British	Engines. 1924	Engines. The North Eastern Marine Engineering Co., Ltd., Sunderland.	Three 17 1/2"	33"	----	163 --- 950 9 1/2 Knots
One	Particulars of Boilers. Description: Cylindrical Multitubular Number: Two Iron or Steel: Steel Loaded Pressure: 180 lbs.	Boilers. British	Boilers. 1924		48"			


PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	1161.50	On account of space required for propelling power	496.20
Space or spaces between Decks ...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Expansion of Trunk ...	14		
Forecastle ...	27.63	These spaces are the following, viz.:-	
Bridge space ...	19.59	Forecastle	71.12
Deep or Break ...	212.50	Bridge	
Side Houses ...	44.77	Round House	
Deck Houses ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Chart House ...		Master's Accommodation	6.14
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	84.49	Boatswain's Store	2.17
Excess of Hatchways ...		Chart Space	4.00
Gross Tonnage ...	1550.62	Fore Peak Tank	33.49
Deductions, as per Contra ...	645.24	After Peak Tank	32.12
Register Tonnage ...	905.38	Total ...	645.24

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 231.45 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 33.00 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Under after end of forecastle L. 2' - 1.64 tons
----- " ----- L. 2' - 4.12 "



Name of Master _____ Certificate of { Service No. Competency No.

No. of Owners _____
Name, Residence, and Description of Managing Owner if there are more owners than one.

H. Harrison (Shipping) Limited
Cory Buildings,
Fenchurch Street,
London.
Shares:- Sixty-four
Dated 24th June 1924.

Bertram Ernest Packington
same address, Manager.

