

CLASS CONTEMPLATED.

G.R. 130.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.Z.D.M.

Official Number. <u>165001</u>	Name of Ship. REIGHTON WYKE	No., Date, and Port of Registry. 9/1937 Hull.		
No., Date, and Port of previous Registry (if any).				
Whether British or Foreign Built. British	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled. Steam Single Screw	Where Built. Selby	When Built. 1937	Name and Address of Builders. Cochrane & Sons Limited Selby.
Number of Decks One & Raised Quarter Deck	Length from fore part of stem, to the aft side of the head of the stern post	Feet. 161	Tenths. 8.	
Number of Masts Two	Main breadth to outside of plank	27	1.5	
Rigged Ketch	Depth in hold from tonnage deck to ceiling amidships	14	2.	
Stem Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	-	-	
Stern Cruiser	Depth from top of deck at side amidships to bottom of keel	-	-	
Build Clincher	Round of beam	-	7	
Framework and description of vessel Steel Trawler	Length of engine room, if any	34	8	

Particulars of propelling Engines, etc., (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Reciprocating Steam Triple Expansion Direct Acting Inverted Cylinder	Engines. British	Engines. 1937	Engines. Charles D. Holmes & Co., Ltd. Hull.	Three 13 1/2"			N.H.P. 120 I.H.P. 750
No. of Shafts.	Particulars of Boilers. Cylindrical multitubular	Boilers.	Boilers.	Boilers.	24"	27"	-	11 3/4 knots
One	Number One Iron or Steel Steel Loaded Pressure 215 lbs	British	1937	Charles D. Holmes & Co., Ltd. Hull.	39"			

Number of water ballast tanks, and their capacity in tons:— Nil


PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	406.88	On account of space required for propelling power	209.28
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	62.15
Turret or Trunk		These spaces are the following, viz.:— Below Deck forward & aft, on raised quarter deck aft, under Forecastle	
Forecastle (Side Houses under)	3.76	(Number of seamen or apprentices for whom accommodation is certified... 18)	
Bridge space		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Pop or Break	22.04	Master's accommodation 6.00	
Side Houses		Chart Space 3.84	21.08
Deck Houses	16.89	Wireless Telegraphy 3.49	
Chart House	3.84	Space	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	11.83	Boatswain's store 7.75	
Excess of Hatchways		Total	292.51
Gross Tonnage	465.24	Cubic Metres.	1316.63
Deductions, as per contra	292.51		827.80
Register Tonnage	172.73		488.83

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 107.76 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 19.78 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.
Open Space under Forecastle Length 26.75 feet = 17.98 tons.

Name of Master	Certificate of Service Competency	No. FEB 1937
No. of Owners		
Name, Residence, and Description of Managing Owner if there are more owners than one.	West Dock Steam Fishing Company Limited having its principal place of business at St. Andrews Dock in the city and county of Kingston upon Hull	
Sixty four (64) Shares.	Ernest Wilfred Robins of St. Andrews Dock Hull designated the person to whom the management of the vessel is entrusted by and on behalf of the owners. Advice received the 25th day of January 1937, under his hand as public officer to West Dock Steam Fishing Company Limited.	
Dated	25th January, 1937	



*940. W.L.17581/626. 500. 8/36. W.y.P.C. 613. 1779. W.L.28798/645. 10*0. 12/36.