

14 SEP 1943

Rpt. C. 11 (Contd.)

Index No. \_\_\_\_\_

# Lloyd's Register of Shipping.

Ship's Name "EMPIRE SWALE" ex "TAKORADIAN".

Official No. 157533.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in \_\_\_\_\_

The following modifications have been effected in an efficient manner, in order to convert the vessel from an "open" to a "closed" shelter deck type:-

- (1) The tonnage opening in shelter deck permanently closed into a welded steel plate 7/16" thick supported by 3-6" x 3" B.A. carlings, a companionway fitted on starboard side, 4'3" x 2'6" with 26" coaming, opening 2'0" x 4'3" with hinged 2" thick wood door operated both sides, and a hatchway on Port side to ammunition locker 2'6" x 2'6" x 3'0" high with a hinged steel watertight lid, toggle fastenings.
- (2) Lifelines of wire rope with stretching screws and fixed eyeplates rigged on shelter deck.

*W. H. B.*

*W. H. Boylan*

SURVEYOR TO LLOYD'S REGISTER.

14 SEP 1943



© 2020

Lloyd's Register  
Foundation

003525-003532-0273