

Lloyd's Register of Shipping.

"EMPIRE SWALE"

157533.

Ship's Name

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

RESTORING OF THE TONNAGE OPENING AS PER LONDON LETTER OF THE 9TH JANUARY, 1946.

The tonnage opening in the Shelter Deck now restored and fitted with efficient wood covers secured on the underside by Rope lashings. ✓

The tonnage openings in the Tonnage Well Bulkhead now closed by 3" boards fitted in channels as originally. ✓

Tonnage well screw down non return valves controlled from the Shelter Deck on P.A.S. sides originally fitted, now overhauled and made good. ✓

Scupper Pipes from tween decks to Machinery Space Bilges have self closing cocks at their lower ends. ✓

Load Line Survey now carried out, markings verified and recut. ✓

New Load Line Certificate and copy issued.

W. E. Marlborough

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

LIVERPOOL.

W. E. Marlborough
4/2/46

