

36321

# LLOYD'S REGISTER OF SHIPPING

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "NOVELIST"

Official No.

Port of Registry Liverpool.

This ship has been under survey at Liverpool.

on September 1958 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~

2 Mechanical ventilation units now fitted each 22" in dia. and .40" thk. with permanent 12" high welded coamings and 3'-6" high portable fan units fitted with external flanges and secured by 18 at  $\frac{3}{4}$ " dia. bolts, each ventilator efficiently stayed and closed by wood plugs and canvas covers, with separate cover plates .40" thk. for closing ventilators when fan units are unshipped.

1 ventilator is fitted on bridge deck port side between frs. 103/104, extended through freeboard deck, and one on freeboard deck in forward well, 4th frame space forward of No.2 hatch starboard side.

Compensation doublers of adequate scantlings have been fitted in way of apertures cut in freeboard and bridge decks.

On completion alterations examined and found satisfactory.

*J. Nugent*

Surveyor to Lloyds Register.

A copy of this Report has been placed on board.

