

# Lloyd's Register of Shipping.

Ship's Name MAHSUD

Official No. 140553

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in JULY, 1932.

The following additional air pipes have been fitted in consequence of a re-arrangement of double bottom tanks for carrying oil fuel.

2 W.I. airpipes on bridge dk. 24" high x 4" dia. from No. 4 DB oil fuel tank

1 " " " " " " x 2 1/2" " "cofferdam between No. 4

for 'd and No. 4aft DB tanks

1 " " " upper dk aft 36" high x 2 1/2" dia., from cofferdam

between No. 6 and No. 7 DB tanks.

All air pipes from DB tanks which carry oil fuel viz: Nos. 2, 3, 4

for 'd 7 and 8 now fitted with wire gauzes. Canvas covers provided

for new cofferdam air pipes.

Hinged shutters on freeing ports as given on original Rpt. C. 11

no longer fitted. Protection bars on these openings are efficient.

(Gls. Dec., 1937).

*Noted  
S.W.B.*

*23/12/37.*



© 2020

Lloyd's Register Foundation