

Rosario 4th. June 1963

THIS IS TO CERTIFY THAT I, William C. Roots, the undersigned
Appointed Acting Engineer Surveyor to Lloyd's Register of
Shipping, did at the Masters Request, attend on board the
vessel:

M/V. "INGER SKOU" - of Danish Flag,
and of 4430 Registered Gross Tons,

whilst lying alongside at Deposits 25-26 of this port, for the
purpose of ascertaining fitness of said vessel's Bilge suction
and make any recommendations relative to same.-

31/5/63 - 0930 hrs.

Inspected Bilge Suctions Port and Starboard in No. 3 - 4 & 5 Holds.
FOUND: Vessel engaged in transporting live-stock between this port
and that of Callao-Peru.- Perforated plates fitted over bilge suction
were becoming obstructed due to animals compressing fodder residues
on same.-

RECOMMENDED: Fitting of filters, fabricated from perforated plate
and constructed angle shaped so as to prevent caking of fodder residues.-

1/6/63 - 1530 hrs.-(Saturday)

Wooden ceilings having been partially lifted Bilge wells were inspected.-
FOUND: Fodder residues had deposited in bilges and would be carried
towards suction.-

RECOMMENDED: At least 5 frame spaces forward of suction to be cleaned
and residues to be removed.- Extra wire mesh filters with flat iron
bar frames to be fitted on an inclined plane in way of first frame
space forward of suction by welding lugs and bolting frames to same so
as to be able to remove for cleaning.- These at No. 3 and 4 Holds.

2/6/63 - 0700 hrs.-(Sunday)

Approved suction boxes filters over No. 3 Port and Stbd. - Tested
suction of pump through lines at 0730 hrs.

Approved suction boxes filters over No. 5 (Hat Boxes) Port and Stbd.
and tested suction at 0830 hrs.

Tested bilge suction of No. 4 Port and Stbd. at 0945 hrs.

3/6/63 - Monday.-

Filter boxes fitted at No. 4 suction at 0300 hrs. on Port side and
at 0730 hrs. on starboard side.-

Extra filter meshes with frames were fitted to No.3 & 4 Suctions by
1500 hrs.


Wm. C. Roots.
ACTING ENGINEER SURVEYOR TO
LLOYD'S REGISTER OF SHIPPING

Lloyd's Register
Foundation

003581-003590-0174