

COPY.

Lloyd's Register of Shipping.

GLASGOW REPORT No. 63260^A

Port

GLASGOW,

16th December, 1940



This is to Certify that

R. DUNSMUIR,

the undersigned Surveyor to this Society did at the request of

the Owners' Representative survey the S.S. "TRADER", 6087 tons gross of Liverpool as she lay in No.1 Govan Dry Dock, Glasgow on the 6th December, 1940 and subsequent dates on account of damage stated to have been sustained through vessel striking quay wall on the 5th December, 1940 when entering the Dry Dock.

On examination found and recommended as follows:-

FOUND

Stem bar set over to starboard side at 16 foot mark and tapering gradually between 14 feet and 19 foot marks.

Shell. Stem Plate E No.1 (P. & S.)

Stem Plate F No.1 (P. & S) set over with stem.

Stem Plate G No.1 (P. & S)

Fore peak tank to test on completion of repairs.
New and disturbed work to be cleaned and recoated.

The above recommendations were made with a view to placing the vessel in as good and efficient condition as before the damage was sustained.

RECOMMENDED

Stem bar to be cropped and part renewed.
Butted top and bottom to existing stem and electric welded.

To be released for access in fitting new stem bar.

To be removed, faired and refitted.

To be cropped and part renewed. New butt raised for access in fitting new stem.

R. Dunsmuir.

Surveyor to Lloyds Register.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."