

27 JUN 1947

Index No.

Lloyd's Register of Shipping.

Ship's Name "EVAN GIBB"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in June 1947

The coamings of cowl and mushroom ventilators have been provided with efficient closing appliances

The 48" diameter open conical top ventilator coamings have been provided with canvas covers

The cowl ventilator coaming 3'-5" high has been specially supported and secured.

The open conical top coaming 9'-6" high has been specially supported and secured.

The open top ventilator coaming 6" x 6" x 12" high marked "E" has been provided with efficient closing appliances.

The air pipes have been provided with efficient closing appliances.

The wires on the guard rails have been set up with stretching screws.

The thickness of the wood hatch covers and their bearing surface is in accordance with Rule Requirements namely 2½" and 3" respectively.

The breadth of the cargo hatchway is 14'-0" and not 15'-9" as stated in the body of the Report.

The Gross Tonnage is 4255 and the Certificate has been amended accordingly.

J. B. Rogers

Noted
27 JUN 1947

Noted on Report C11
R.B.

112 AUG 1947

ML-D



© 2020

Lloyd's Register
Foundation

003649-003658-0192