

"LUCANIA"

To complete SS (Hull) for a record of SS.Gen.10,57 (Dr):-

Plating of strength deck to be drilled and gauged.

To be examined

No.2 DB tank, DB lub.oil tank frs.42-47

DB tank frs.62-64.

To be tested

OF wing tanks Nos.1, 3, 5, 6, 11, 12, 17.

FW wing tanks Nos.2 and 4

FW tanks frs.33-39 and frs.144-153.

Freeboard marks to be verified

To complete Main Boiler Survey for a record of MBS 4,58:-

Port forward and starboard forward boilers to be examined throughout. Port centre and starboard center boiler mountings to be examined. Safety valves of all boilers to be adjusted and the oil fuel installation to be examined under working conditions.

Hull subject:-

Corroded rivets in lower edge of third strake below sheer (port and starboard amidships) to be dealt with by completion of the Special Survey.

Machinery subject:-

The starboard screw and tubeshafts to be renewed before the end of May, 1959, also to the new de-superheater installation being examined under working conditions on the vessel's return to Genoa from the present voyage (2 months' limit).



© 2021

Lloyd's Register
Foundation

003687-003697-0274