

# Lloyd's Register of Shipping.

Ship's Name REDRIFF

Official No. 148620

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in JUNE, 1932.

NO.1 hatch 3 hatch beams renewed complete with mounting angles.

Plates 23" x .40, angles 4"x 3" x .45".

No.3 hatch. 3 hatch beams renewed complete with mounting angles.

2 beams 21 $\frac{1}{2}$ " x .40 angles 6" x 3" x .50".

1 beam 22" x .45 with welded flat plate top and bottom 12 $\frac{1}{4}$ " x .60" I

No.4 hatch 2 hatch beams renewed complete with mounting angles, 2020

plates 23" x .40 angles 6"x 3" x .50" B.A. and 4" x 3" x .45 JH

45 hatch covers, 43 hatch cleats 2 bunker hatch rest angles renewed.

003788-003799-0060

Lloyd's Register Foundation

Coop Bulkhead	...	...	...	no work															
Raised Quarter Deck Bulkhead	...	...	...	.30	.30	5x3x $\frac{1}{2}$ or 3x2 $\frac{1}{2}$ x $\frac{3}{4}$ OA.	5-0 52-6	None.	ALTER. one 4-6x2-0	1-7	2-0								