

COPY.

Lloyd's Register of Shipping.



United with
THE
BRITISH
CORPORATION
REGISTER.

Port

CAPE TOWN

26th October, 1951.

Coils annealed and tested.

This is to certify that

J. A. van LARE,

(Signed) J. A. van LARE.

undersigned Surveyor to this Society did at the request of Owners Representative, survey the Boilers and Evaporator of the Whaler "EUGENE VINKE" (A.M.10), 721 tons gross, of Amsterdam, on the 1951 refit, and beg to report as follows:

FORWARD BOILER: On the 8th May and 1st June, 1951, the boiler examined internally and externally, together with safety valves, mountings, manholes, doors and their fastenings, and all found or placed in good condition.

The safety valves afterwards adjusted under steam to lift at 225 lbs per square inch.

Height of safety valve compression rings: Port .448"
Stbd. .392"

WATERS: All plain tubes renewed, were pitted.
Two bottom rows of c.c. stays, between Port and Centre combustion chamber renewed, corroded.
On completion of repairs the boiler examined under hydraulic pressure.

REAR BOILER: On the 8th May and 13th June, 1951, the boiler examined internally and externally, together with safety valves, mountings and manholes, doors and fastenings, and all found or placed in good condition.

The safety valves afterwards adjusted under steam to lift at 15 lbs per square inch.

Height of safety valve compression rings: Port .317"
Stbd. .328"

WATERS: All plain tubes renewed, were pitted.
Eleven c.c. of centre box back plate renewed, corroded.
On completion of repairs the boiler examined under hydraulic pressure.

EVAPORATOR:


On the 1st June, 1951, the Evaporator examined internally and externally, together with safety valves and mountings, and all found in good condition.

/OVER ...

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

While the Committees of the Society use their best endeavours to ensure that the functions of the Society are executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or Certificate issued by the Society or its Members, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.

2000 3/50



© 2020

Register
Foundation

003948-003957-0216 1/2

0216 1/2

al Damage or Repair Fee (if any) £ : :
(per Section 29)

(2)

Rpt. 10.

S.W. "EUGENE VINKE" (A.M.10)

Safety valves afterwards adjusted under steam to lift at 20 lbs per square inch.

Height of safety valve compression rings: Forward .630"
Aft. .723"

Coils annealed and tested.

(Signed) J. A. van LARE.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.



© 2020

Lloyd's Register
Foundation

0216 2/2