

Lithgow's Ltd.

Yard No. 958. ("Y1" type)

Received from Chief Surveyors

Sent to Chief Surveyors

VESSEL'S NAME

EMPIRE BAFFIN

Report

Grk

No. 21587

For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR.

(In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report. 24/5/92.)

Nature of Survey

FIRST ENTRY

~~When due~~

This is the first vessel of the "Y1" type design and is generally a sister to the "EMPIRE FROST" etc. constructed by the same Builders to the "Y" type design except that a forecabin has not been fitted and other small amendments made.

The scantlings are suitable for a draft of 18" in excess of that corresponding to the freeboard which could be assigned if a tonnage opening were fitted.

The tank top plating has been increased in thickness under the hatchways in lieu of ceiling.

100A1 With freeboard ✓

2 Dks ✓

Cell DB 370' 1215t, FPT 122t, APT 172t ✓

FK, 7BH (Coll to W dk, 6 to 2nd dk); 5 divisional W.T. BHs in 'tween dks. pt. Cem., Lloyd's A & CP. ✓

O.L. 446.0'

at
E/S/D

The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed, and that cargo battens and hatch covers at the 2nd deck will be fitted at the first available opportunity.

J.C.D.
.....
22.10.41

Insert in S.R.L: - (One bower anchor and 45 fathoms of chain cable to be supplied when the present state of emergency has passed).
Cargo battens and hatch covers at 2nd dk to be fitted at first available opportunity.

It is concluded the 15" x 4" x 42" channel frames fitted from $\frac{1}{2}$ length forward to 75% length from stem are as approved, but this should be confirmed.

004019-004028-0104