

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

^{"DELWIND"} ~~ex~~ ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "MUTLAH" Official No. -182076- 1831

Port of Registry ~~LONDON~~ MANROVIA

This ship has been under survey at LONDON

on March, 1958 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~

Hatch 4'6" x 4'6" fitted on Shelter deck P.S. over Tonnage Well space which is to be used as a bunker for Galley Coal.

The hatch coaming is of steel 32" high x .50" thick. Wood hatch covers 2 1/2" thick, 2 tarpaulins, battens and wedges have been supplied and seen in place.

The existing scupper valves P&S. in Tonnage Well space have been removed and shell plating blanked off.

Drain holes (1P& 1S) fitted in forward bulkhead of Bunker (Tonnage well space).



Noted
all
16.4.58

A copy of this Report has been placed on board.

