

Lloyd's Register of Shipping.

Ship's Name M. V. "SOMMELSDIJK"

Official No. --

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in --

ALTERATIONS COMPLETED AT SAN FRANCISCO, FEBRUARY 23, 1943.SANITARY DISCHARGES

Additional sanitary discharges fitted from:-

Hospital - Port No. 1 upper tween deck.

Toilet and Wash Room - Port No. 2 upper tween deck.

Troop Galley - Port and Starboard upper tween deck.

Toilet and wash room - Port No. 6 upper tween deck.

These discharge overboard below the second deck, and a cast steel non-return
clapper valve is fitted at each outlet in way of ship's side. An approved
cast steel bodied positive action gate valve is bolted to each clapper valve;
and extension rods with indicating hand wheels, and operated from upper tween
deck, are connected to the gate valves. Rods are made flexible by the use of
universal joints.

M. Blegg

N. B.
8.2.43.
8.4.43.