

11 NOV 1942

Index No. 8602 35384

Rpt. C. 11 (Contd.)

# Lloyd's Register of Shipping.

Ship's Name T.S.M.V. "SOMMELSDIJK" Official No. 32440

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in -

Alterations completed at San Francisco, California, August 27th, 1942.

## COMPANIONWAYS

Strongly constructed steel companionways readily opened from both sides fitted at the corners of the Shelter Deck Hatchways - Two (2) on Nos. 1, 2, 4, 5 and 6 hatchways - One (1) on No. 3. These companionways welded to hatch coaming and hatch beam adjacent to coaming. Efficient arrangements made to batten tarpaulins in way of companionways.

## SANITARY DISCHARGES

Additional sanitary discharges fitted from Hospital in No. 1 Upper Tween Deck and Washplace in No. 6 Upper Tween Deck. These discharge overboard below the second deck, one cast steel clapper valve fitted at each outlet.

J. Rennie  
Aug 27<sup>th</sup> 1942



© 2020

Lloyd's Register Foundation  
004042-004048-0156