

Attached & GENOVA Rpt N° 22867 16 DEC 1957

Rpt. C. 11 (Contd.)

Index No. _____
(For London Office use)

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "NASSAU" Official No. _____

Port of Registry Monrovia

This ship has been under survey at Genoa

on November 1957 and the following alterations to the conditions of

assignment of loadlines have now been effected ~~found~~—

- 1) N°4 hatchway on the Promenade Deck, portable swimming pool removed, coamings removed and opening in deck permanently closed by means of welded steel plating stiffened by beams.
- 2) N°5 hatchway on the Promenade Deck, coamings removed and the swimming pool, which was previously fitted in N°4 hatch, now fitted inside N°5 hatch, connecting it to the ship's structure flush with deck, permanently closing the hatch opening.
- 3) N°5 hatchway flush on "P" deck (next below Promenade Deck), opening permanently closed by means of steel plating welded to deck and to boundary plating of swimming pool fitted in the corresponding hatchway on deck over
- 4) N°6 hatchway on Promenade Deck, coamings removed and existing portable swimming pool now permanently connected to the ship's structure, flush to deck, permanently closing the hatch opening. An opening cut in bottom of swimming pool, dimensions 3 x 3 metres fitted with flush, steel, W.T., bolted cover.

Finigo

A copy of this Report has been placed on board.

© 2021
 Voted 21.1.58
 Lloyd's Register
 Founder

004170-004176-0041
 004170-004176-000