

LLOYD'S REGISTER OF SHIPPING

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "IVY FAIR" (ex "CARLTON") Official No. 165841

Port of Registry Newcastle

This ship has been under survey at Barry, Glam.

on 11th April, 1963 ~~1962~~ and the following alterations to the conditions of assignment of loadlines have now been effected ~~by the Board~~

The vessel has been modified from open to closed shelter deck condition :-

Tonnage hatch wood covers have been removed and hatch closed by a steel plate 3/8" thick suitably stiffened and welded to the hatch coaming.

The tonnage well 5" s.d. drain valves (port and starboard) have been permanently closed by welded plates on the ship's sides,

Hatch locking bars have been provided for all hatches on the upper deck.

Lifelines and fittings provided.

The tonnage openings in the shelter deck bulkheads have not been closed by agreement with the Owners' Superintendent except the bulkheads between Nos. 1 and 2 tween decks and Nos. 4 and 5 tween decks.

Old freeboard markings port and starboard now obliterated and new assigned freeboards cut in and painted on the ship's sides, port and starboard. New marks verified.

L. R. M. O. S.

Lloyd's Register of Shipping,

CARDIFF. 16th April, 1963.

*Noted ✓
L.R.
24/4/63*

5

A copy of this Report has been placed on board.

