

26 JUL 1950

36895

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name S.S. "CARLTON"Official No. 165841

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1942.

This vessel has now been converted to O.F. burning and the alterations and additions arising from this conversion are as follows:-

No. 3 main cargo hatchway on foreboard deck dispensed with - now forms crown of new bunkers. Coal trimming hatches - 1 P.S. on foreboard deck plated over, with B.A. coaming retained.

One flush O.T. and W.T. manhole, 18"x12", fitted in foreboard deck to each bunker and to forward deep W.B. tank P.S. respectively. One long stud, clenched at top fitted to each manhole and 4" protection plate welded to deck round each manhole. Flood covers also supplied and fitted over area of manhole.

New airpipes fitted in shelter deck as follows:-

No. 2 and 3 D.B. tanks (O.F.) - 3 1/2" dia - 30" above deck.

Deep bunkers P.S. and pentas - 6" - - 36" - -

Closing arrangements for above - wire gauge and canvas covers.

Deep water ballast tanks forward - 4" dia. - 30" above deck.

Deep " " tank aft - 4" dia. - 30" - -

Closing arrangements for above - wood plugs & canvas covers.

H. Macfarland
Swire
28-6-50

Copy of above attached to C.11 and placed on board.

Attest
At.

28 JUL 1950