

Lloyd's Register of Shipping.

Ship's Name "CLAN MACIVER"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

Temporary alterations for gunners' accommodation.

It was reported that the portable steel scuttle fitted on No. 3 hatchway for access to the gunners' accommodation was not watertight.

On examination at Port Natal it was recommended that the batten cleats on sides of scuttle be altered to allow the tarpaulins to fit closer, extra holding down bolts to be fitted in base angle of scuttle and two steel sealing plates to be fitted at base of scuttle and electrically welded.

The above repairs have been efficiently carried out.

(Signed) T. H. Noel.

18th Jan. 1942.

PORT NATAL.

*Noted
HNB
27/3/42*



© 2020

Lloyd's Register
Foundation