

SCALE :- $\frac{1}{2}" = 1 \text{ FT}$



LONGITUDINAL FRAMING AT BOTTOM & DECK.

LLOYDS NUMERALS.

D	= 34	= 34.0
L x D	= 463 x 34	= 15742.0
L (B + D)	= 463 (61.5 + 34)	= 44216.5.
L / D	= 463 ÷ 34	= 13.62

EQUIPMENT NUMERALS		
2 ND LONG NUMERAL L (3.0)		44216.5
POOD	93.5	
BRIDGE	44.5	
FORECASTLE	54.5	
	192.5	2.75
		115.50
POOD HOUSE		
5.0 CABIN	95.5	
BRIDGE HOUSE	55.5	
	151.25	0.5
		565.0
OFFICERS HOUSE	48.0	
	48.5	
WHEEL HOUSE	30.5	
	127.5	0.5
		586.0
EQUIPMENT NUMERALS		586.5

EQUIPMENT LIST				
2' BOWER ANCHORS	3 1/2 CWT	STOCKLESS.		
1 STRAW	63 1/2			
100 FMS	2 1/2	STUD LINK CHAIN CABLE		
10 1/2	4 1/2 (3/24)	CIRC. STEEL WIRE GALV?		
120	5 1/2 (2/24)			
2 @ 100 FMS	3 (2/24)	WIRE HANDS, BUILDERS SUPPLY		
5 @ 100	5 1/2 (2/24)		OWNERS	
HANDS OF SPECIAL MANILA				

SECTION THRO' WING TANKS
AT INTERMEDIATE FRAMES
LOOKING AFT.

SHELL THICKNESSES AT ENDS. BOTTOM
CLEAR OF OIL & STRENGTHENING OF BOTTOM
FORWARD OF 1/2 L OR 2
BOTTOM - .69 FOR 1/2 L TO .50 AT ENDS
SIDE - .67 " " " .47 " " } FOR RULE FRAME SPACING

TYPICAL SECTION AT TRANSVERSE LOOKING AFT.

RIVETING NOTE :-
RIVETS IN SIDE FRAMES TO SHELL SPACED 6 DIA° APART IN WAY OF OIL TANKS.
RIVETS IN SIDE FRAMES TO SHELL SPACED 6 DIA° APART IN WAY OF
PEAK TANKS, DEEP TANK & OIL FUEL BUNKER.
RIVETS IN SIDE FRAMES TO SHELL (EXCEPT 4 OTHERWISE MARKED)
7 DIA° APART WHERE FRAME SPACING DOES NOT EXCEED 23 1/2".
9/8 DIA° APART WHERE FRAME SPACING EXCEEDS 23 1/2" BUT
NOT EXCEED 31 1/2".
RIVETS IN SIDE FRAMES TO FLOORS SPACED 7 DIA° APART CLEAR
OF OIL TANKS, DEEP TANK & OIL FUEL BUNKER.
RIVETS IN SHELL BEAMS SPACED 4 DIA° APART THROUGHOUT.

[illegible]

9

42°

42°

12

BOTTOM TRANSVERSE

12

12

BOTTOM

LONG

DETAIL OF TRIPPING SKIRT

BRACKETS FITTED MIDWAY
BETWEEN TRANSVERSALS A
BETWEEN TRANSVERSALS A
BULKHEAD.

42" BRACKET, 2 PLANGE
WELDED TO CENTRE GIBBER
A SHOWN.

DETAIL OF CENTRE GIBBER
TRIPPING BRACKET.


M V. BRITISH PREMIER ★

LITHGOWS No 1052

MIDSHIP SECTION AS BUILT

Ground Test Entry Report No. 24366.

RECORDS DEPT.,
LONDON



RETAIN



© 2020

Lloyd's Register
Foundation

004230-004237-0182