

65. Owners Scottish Shire Line L
tails of casualty

Date of Build 5-1957

Owners Reply

7.5.65. Owners Scottish Shire Line Ltd.

Details of casualty

+ 100A1	+ LMC CS8,61
10,64	BS M 2,63
ss 3,61	d12,64
	sp 7,63
+ Lloyd's RMC	ts 2,63 CL

This ship stranded at Abd-al-Kuri and has been abandoned as a total loss.

The owners concur.

Date of casualty 23rd March, 1965.

12 42 p.m., local time, Mar. 23: In
12 8 N., long. 52 17 E., struck
submerged rock south of Abd-al-Kuri,
please stand by.

At 1 54 p.m., local time: Ship making water and may require assistance.

AYRSHIRE. — London, Mar. 24. — The following advice was received to-day from steamer Ayrshire: Beached Abdal-Kuri on sandy bottom; position safe at present. Holed in Nos. 2, 3 and 4 double bottoms and starboard bilge. 23 ft. water No. 2, 21 ft. Nos. 3 and 4 double, holed engine-room double bottom, engine-room dry. Require salvage assistance.

The following advice was received to-day from the owners' agents in Aden: Ayrshire reports: Holed Nos. 2, 3 and 4 holds and double bottoms and engine-room double bottom. Water in Nos. 2, 3 and 4 holds. Engine-room dry. (See issue of Mar. 24.)

London, Mar. 24. — Steamer Ayrshire, cargo general: Owners advise contracting with L. Smit & Company on Lloyd's Open Form. Salvage operations expected to commence in four to five days.

—London, Mar. 24.—
 Ayrshire: The London agents
 L. Smit & Co. have received the following message, dated Rotterdam, Mar. 24: L. Smit & Co. have contracted on Lloyd's Open Form the salvage of the Ayrshire, aground at Abd-al-Kuri. Their tug Ocean is expected to arrive at the vessel in approximately four and a half days' time. Tug Poolzee is due at Aden in approximately six days' time, where she will take on necessary salvage equipment. Smit's salvage inspector, Mr. Colthoff, is flying to Aden to-morrow, together with the owners' representative. They will proceed from there to the vessel.

SOURCE OF INFORMATION

YRSHIRE.—London, Mar. 25.—Following received from the master of steamer *Ayrshire*, timed 5 20 p.m., Mar. 24: Passengers and crew all well. Conditions do permit transfer of passengers by motor boat. Generators are fully operative. Starboard diesel tank damaged, 64 tons of diesel fuel in port tank. Rate of ingress of water in Nos. 2, 3 and 4 holds was greater than pumps could deal with while keeping engine-room dry, therefore decided to beach. Had trouble with choked strums; this now rectified and nesting bilge lines duct keel full. Starboard fresh-water tanks damaged. Fresh water on board boiler 70 tons, domestic 100 tons, all on port side ship. Beached on sandy bottom, lying comfortably, in no immediate danger. Fresh-water ballast in reserve in peaks 150 tons. (See issue of Mar. 25.)

AYRSHIRE. — Aden, Mar. 24.—Steamer Ayrshire: Understand from Port Officer H.M. tank landing ship Anzio sailing on Mar. 25 for Mombasa and calling casualty en route for assistance. Understand from owners' agents steamer Clan Mactaggart standing by and motor vessel Clan Malcolm on way.—Lloyd's Agents per Salvage Association. (See issue of Mar. 26.)

AYRSHIRE.—London, Mar. 30. — The following messages have been received by the owners of steamer Ayrshire from the master:

Timed 12 20 p.m., Mar. 28: Engine-room after bulkhead leak negligible, tank top intact, forward bulkhead split in two places, 18 in. long, in way of duct. Keel leak considerable, 100 lb.

Apr	Willa, Szczecin, R. A. Burke.
Apr	Ursula Bloch, Oslo, G. Bell & Co.
Apr	Tito, Amsterdam, Palgrave Murphy.
Apr	Tina, Kolka, Palgrave Murphy.
Apr	Tomasz, Belia, Irish Shipping.
Apr	Selectivity, Oslo, G. Bell & Co.
Apr	St. Michael, Cyprus, Connolly Shaw.
Apr	Rachlin Head, St. John (N.B.), Palgrave.
Apr	Ramore Head, Hampton Roads, Palgrave.
Apr	Pleiss, Yokohama, Palgrave Murphy.
Apr	Pellium, Curacao, G. Bell & Co.
Apr	Palestine, Liverpool, Irish Shipping.
Apr	Lake Atlin, British Columbia, R. A. Burke.
Apr	Knapman River, Duxia, R. A. Burke.
Apr	Irena, Baltic, G. Bell & Co.
Apr	Inga Bastien, Casablanca, G. Bell & Co.
Apr	Geeststet, W. Indies, G. Bell & Co.
Apr	Gee, Norrköping, G. Bell & Co.
Apr	Gallia, Hampton Roads, —.
Apr	Guinea, Bahia, Connolly Shaw.
Apr	Buenos Aires, G. Bell & Co.
Apr	Buenos Aires, G. Bell & Co.

Aden, Mar. 30.—
Steamer Ayrshire: Master reports on
Tuesday morning (Mar. 30) leakage
forward bulkhead of engine-room
increased but still amply controllable by
ship's pumps. Some further damage to
starboard boiler seating connection due
to slight movement of vessel. Pumping
test of No. 2 lower hold indicates leak-
age controlled by one pump. Ship's
crew jettisoning bags of salt after bleed-
ing. Am proceeding to casualty on tug
Poolzee at noon on Mar. 31 with owners
and Smit's representative, expecting to
arrive at casualty on Friday morning.—
Salvage Association's Salvage Officer.

AYRSHIRE.—London, Mar. 31.—The owners of steamer Ayrshire have received the following message from the master, dated Mar. 31: No change in condition. Pumping out continued overnight, progress in Nos. 2, 3 and 4 satisfactory. Jettisoned 96 tons of salt yesterday, jettisoning chemicals ex No. 1 to-day. Attempt to refloat this morning stopped by breaking of towrope; will try again to-night at high water. (See issue of Mar. 31.)

London, Mar. 31. — The owners of the steamer Ayrshire have received the following message from the master of the Ocean, dated Mar. 31: Water level substantially lowered Nos. 2, 3 and 4 holds. Ship bumping slightly. Made effort to refloat this morning but unsuccessful, will try again this evening and hopeful. View bumping. Ayrshire has emptied both boilers. If refloated, Ayrshire will remain in close vicinity ready for re-beaching if necessary. Tug Noordzee will call at Ayrshire on Friday (Apr. 2) and supply more portable pumps. Tug Poolzee sails this evening with additional pumps on board, estimated time of arrival at Ayrshire noon on Friday.

Steamer Ayrshire: Latest reports via master of tug Ocean indicate water levels Nos. 2 and 3 lower holds substantially lowered by pumping and that No. 4 lower hold is also pumpable. It now appears that refloating on to-night's tide is possible and if vessel refloated she will remain close to present condition until arrival of tug Poolzee at site about noon, Apr. 2, when further decisions will be taken. Both boilers of Ayrshire are now emptied but full auxiliary power is available for pumps, winches, &c. Leaving Aden on Poolzee at 7 p.m. to-day.—Salvage Association's Salvage Officer.

Suggested record "WRECKED 3.65"

Date of Committee

Minute

1,000,12,61 (MADE AND PRINTED IN ENGLAND)

Noted By Publications

FRIDAY 14 MAY 1965

Wrecked 3.65

(Delete Rmc class)

NOTED FOR
POSTING

REPORT OF TOTAL LOSS, CASUALTY, BREAKING UP, ETC.

Ship's Name SS/MS "AYRSHIRE" RMC
 Casualty notice sent to Owners 5.5.65. Owners' Reply 7.5.65.

Gross tons 9424

Date of Build 5-1957

Owners Scottish Shire Line Ltd.

Details of classification

+100A1	+LMC CS8,61
10,64	BS M 2,63
ss 3,61	d12,64
	sp 7,63
+Lloyd's RMC	ts 2,63 CL

Details of casualty

This ship stranded at Abd-al-Kuri and has been abandoned as a total loss.

The owners concur.

Date of casualty 23rd March, 1965.

SOURCE OF INFORMATION

AYRSHIRE. — Aden, Mar. 23. — Following S O S received from master of steamer Ayrshire (Liverpool for Brisbane):
 1 42 p.m., local time, Mar. 23: In 12 8 N., long. 52 17 E., struck submerged rock south of Abd-al-Kuri, please stand by.
 At 1 54 p.m., local time: Ship making water and may require assistance.

AYRSHIRE. — London, Mar. 24. — The following advice was received to-day from steamer Ayrshire: Beached Abd-al-Kuri on sandy bottom; position safe at present. Holed in Nos. 2, 3 and 4 double bottoms and starboard bilge, 23 ft. water No. 2, 21 ft. Nos. 3 and 4 double, holed engine-room double bottom, engine-room dry. Require salvage assistance.

The following advice was received to-day from the owners' agents in Aden: Ayrshire reports: Holed Nos. 2, 3 and 4 holds and double bottoms and engine-room double bottom. Water in Nos. 2, 3 and 4 holds. Engine-room dry. (See issue of Mar. 24.)

London, Mar. 24. — Steamer Ayrshire, cargo general: Owners advise contracting with L. Smit & Company on Lloyd's Open Form. Salvage operations expected to commence in four to five days.

London, Mar. 24. — Steamer Ayrshire: The London agents L. Smit & Co. have received the following message, dated Rotterdam, Mar. 24: L. Smit & Co. have contracted on Lloyd's Open Form the salvage of the Ayrshire, aground at Abd-al-Kuri. Their tug Ocean is expected to arrive at the vessel in approximately four and a half days' time. Tug Poolzee is due at Aden in approximately six days' time, where she will take on necessary salvage equipment. Smit's salvage inspector, Mr. Colthoff, is flying to Aden to-morrow, together with the owners' representative. They will proceed from there to the vessel.

AYRSHIRE. — London, Mar. 25. — Following received from the master of steamer Ayrshire, timed 5 20 p.m., Mar. 24: Passengers and crew all well. Conditions do permit transfer of passengers by motor boat. Generators are fully operative. Starboard diesel tank damaged, 64 tons of diesel fuel in port tank. Rate of ingress of water in Nos. 2, 3 and 4 holds was greater than pumps could deal with while keeping engine-room dry, therefore decided to beach. Had trouble with choked strums; this now rectified and nesting bilge lines duct keel full. Starboard fresh-water tanks damaged. Fresh water on board boiler 70 tons, domestic 100 tons, all on port side ship. Beached on sandy bottom, lying comfortably, in no immediate danger. Fresh-water ballast in reserve in peaks 150 tons. (See issue of Mar. 25.)

AYRSHIRE. — Aden, Mar. 24. — Steamer Ayrshire: Understand from Port Officer H.M. tank landing ship Anzio sailing on Mar. 25 for Mombasa and calling casualty en route for assistance. Understand from owners' agents steamer Clan Macgarratt standing by and motor vessel Clan Malcolm on way. — Lloyd's Agents per Salvage Association. (See issue of Mar. 26.)

AYRSHIRE. — London, Mar. 30. — The following messages have been received by the owners of steamer Ayrshire from the master:

Timed 12 20 p.m., Mar. 28: Engine-room after bulkhead leak negligible, tank top intact, forward bulkhead split in two places, 18 in. long, in way of duct. Keel leak considerable but contained by ship's pumps; will require stud patches. Ingress of water to No. 2 hold much less than Nos. 3 and 4 holds. Bottom damage confined to starboard side. Naval diver's inspection vessel evenly supported along entire length. No. 1 tank pierced by rock when beaching. No damage to shell plating above bilge keel. Eight holes in bottom plating in way of Nos. 2 and 3 double bottom tanks. Riveted seam in way of Nos. 4 and 5 double bottom tanks open for 30 ft., approximate 4-in. gap. Inspection limited to turn of bilge only. Reason to suspect more damage towards centreline. Commenced opening hatches. Received fresh water from H.M. tank landing ship Anzio.

Dated Mar. 29: Tug Ocean alongside at 10 45 a.m., G.M.T., preparing to pump.

Dated Mar. 30: Condition of engine-room deteriorating due to slight movement of vessel. Leak in forward bulkhead increasing and bolted connection of starboard boiler outboard longitudinal seating breaking loose due to distortion of tank top. Plenty of reserve in engine-room pumps, but would suggest you expedite arrival of tug Poolzee and commencement of actual salvage operation. Water in No. 2 hold under complete control with one pump. Fifty tons of diesel on board, no supplies required. Jettisoning salt to-day.

Owners advise Poolzee and coaster and salvage team expect to arrive alongside at daylight on Friday morning (Apr. 2). (See issue of Mar. 27.)

Aden, Mar. 30. — Steamer Ayrshire: Master reports on Tuesday morning (Mar. 30) leakage in forward bulkhead of engine-room increased but still amply controllable by ship's pumps. Some further damage to starboard boiler seating connection due to slight movement of vessel. Pumping test of No. 2 lower hold indicates leakage controlled by one pump. Ship's crew jettisoning bags of salt after bleeding. Am proceeding to casualty on tug Poolzee at noon on Mar. 31 with owners and Smit's representative, expecting to arrive at casualty on Friday morning. — Salvage Association's Salvage Officer.

AYRSHIRE. — London, Mar. 31. — The owners of steamer Ayrshire have received the following message from the master, dated Mar. 31: No change in condition. Pumping out continued overnight, progress in Nos. 2, 3 and 4 satisfactory. Jettisoned 96 tons of salt yesterday, jettisoning chemicals ex No. 1 to-day. Attempt to refloat this morning stopped by breaking of towrope; will try again to-night at high water. (See issue of Mar. 31.)

London, Mar. 31. — The owners of steamer Ayrshire have received the following message from the master of the Ocean, dated Mar. 31: Water level substantially lowered Nos. 2, 3 and 4 holds. Ship bumping slightly. Made effort to refloat this morning but unsuccessful, will try again this evening and hopeful. View bumping, Ayrshire has emptied both boilers. If refloated, Ayrshire will remain in close vicinity ready for re-beaching if necessary. Tug Noordzee will call at Ayrshire on Friday (Apr. 2) and supply more portable pumps. Tug Poolzee sails this evening with additional pumps on board, estimated time of arrival at Ayrshire noon on Friday.

Aden, Mar. 31. — Steamer Ayrshire: Latest reports via master of tug Ocean indicate water levels Nos. 2 and 3 lower holds substantially lowered by pumping and that No. 4 lower hold is also pumpable. It now appears that refloating on to-night's tide is possible and if vessel refloated she will remain close to present condition until arrival of tug Poolzee at site about noon, Apr. 2, when further decisions will be taken. Both boilers of Ayrshire are now emptied but full auxiliary power is available for pumps, winches, &c. Leaving Aden on Poolzee at 7 p.m. to-day. — Salvage Association's Salvage Officer.

Suggested record

Date of Committee

Minute

1,000,12,61 (MADE AND PRINTED IN EN

No

Y 1965

Lloyd's Register

NOTED FOR POSTING

Aden, Apr. 1.—Steamer Ayrshire: Tug Poolzee arrived here on Mar. 31 and left the same day.

AYRSHIRE. — London, Apr. 3. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 2: Tug Poolzee party arrived Ayrshire at 5 p.m., G.M.T., also motor coaster Seivun. (See issue of Apr. 3.)

AYRSHIRE. — London, Apr. 5. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 3: Salvors advise five six-inch and five three-inch pumps being dispatched by air to Aden on Apr. 5. Divers' examination of starboard side to-day shows vessel resting on rock and sand from forward to after end of No. 5 hold. Pumping presently being regulated to keep vessel solidly aground. Steamer "Nicolas" to lighten majority of remainder of sound cargo; meantime, discharging continued from Nos. 2 and 3 shelter decks into motor coaster Siyoun. Weather south-easterly, force 4 (moderate breeze), slight sea and swell. Vessel lying quietly. (See issue of Apr. 5.)

Apr. 5.) — London, Apr. 5. — The owners of steamer Ayrshire have received the following message from the master, timed 5 24 p.m., Apr. 3: Divers examination starboard side vessel resting evenly on rock and sand from forward to No. 5 hatchway, aft of which unsupported. Salvors advise 10 extra pumps being flown chartered aircraft Rotterdam-Aden early next week; instruct master of motor vessel Clan Maclean on-carry and rendezvous here with tug. Meantime, pumping suspended Nos. 2 and 4 to retain vessel in present firm position. Vessel still lying comfortably. Discharge of cargo into coaster from Nos. 2 and 3 shelter decks nearly complete, start No. 4 shelter deck tomorrow. Steamer Ais Nicolas, 6,000 tons deadweight, estimated date of arrival Wednesday (Apr. 7) for discharge balance undamaged cargo, excluding heavy lifts.

heavy lifts. London, Apr. 5. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 4: Continued discharging from shelter and 'tween decks into motor vessel Seiyun. Salvors working on

bottom damage where accessible.
Weather south-easterly, force 4
(moderate breeze), slight sea and
swell. Vessel lying quietly.

AYRSHIRE.—London, Apr. 6.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 5: Discharging continued from upper decks into motor vessel Seiyun, which completed and sailed for Aden at 1 p.m. Salvors continued work on bottom damage. Jettisoning chemicals from Nos. 1 and 6 and egg fillers from No. 2. Weather south-easterly, force 3 (gentle breeze), slight sea and swell. Vessel lying quietly. (See issue of Apr. 6.)

AYRSHIRE.—London, Apr. 7.—The Salvage Association have received the following radio message from their salvage officer on board steamer *Ayrshire*, dated Apr. 6: Double bottom tanks No. 4 starboard centre, No. 4 port centre and No. 5 port all found to be contaminated by salt water this morning, otherwise hull position unchanged. Waterlogged oil-stained bales jettisoned from No. 3 and paper sacks of calcium carbonate from No. 6 hold. Weather south-easterly, force 3 (gentle breeze), slight sea, swell slightly increased. Vessel lying quietly. Lighter steamer *Ais Nicolas* expected to depart from Aden for *Ayrshire* on Apr. 7. Aden agents report. (See issue of Apr. 7.)

owners of steamer Ayrshire have received the following messages from the master:

Time 8 18 a.m., Apr. 6: Condition of engine-room unchanged. No. 4 double bottom port and starboard inner tanks and No. 5 double bottom port and starboard common to sea. Fresh water pressure system discontinued. Rationing from peaks. Steamer 'Ais Nicolas' delayed repaired Aden. Cory (owners' agents at Aden) advise steamer Nunzia may be available. Stop jetstion further cargo owing to possibility of fouling access alongside. Urgently require coaster for lightening.

Time 8 a.m., Apr. 7: Condition of engine-room still unchanged. No definite news Ais Nicolas. Nunzia definitely not available. To-day's amended cargo distribution No. 5 upper 'tween deck 90 tons, No. 6 lower hold 220 tons. Morale and health remain good. Weather light SE, wind, slight swell.

AYRSHIRE. — London, Apr. 8. — The Salvage Association have received the following radio message from their salvage officer on board steamer *Ayrshire*, dated - Apr. 7: Continued jettisoning paper sacks lime from No. 6 hold. Weather light airs, smooth sea, long low swell. Vessel lying quietly. (See issue of Apr. 8.)

AYRSHIRE. — London, Apr. 9.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 8: Position unchanged. Vessel lying quietly. Further jettisoning of bricks from No. 4 'tween deck carried out. Steamer Ais Nicolas left Aden at 8 15 a.m., G.M.T., to-day and is due here in morning of Apr. 10. Weather light variable winds, smooth sea, light swell. (See issue of Apr. 9.)

London, Apr. 9.—Steamer Ayrshire: The owners' agents at Aden advise: Steamer Ais Nicolas sailed at 11 45 a.m., Apr. 8, with engineers pumps machines on board, estimated time of arrival at Avrshire 6 a.m., Apr. 10.

AYRSHIRE. — London, Apr. 10. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 9: Position materially unaltered. Continued jettisoning bricks from Nos. 1 and 4 'tween decks and preparing cargo for transfer to steamer Ais Nicolas, whose arrival now reported morning of Apr. 11. Weather light airs, smooth sea, slight swell; vessel quiet. (See issue of Apr. 10.)

AYRSHIRE. — London, Apr. 12. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 10: Position remains unchanged. Completed jettisoning pallets firebricks from No. 1 'tween deck. Remaining holds ready for discharge into lighter steamer, which now due 2 a.m., G.M.T., Apr. 11. Light variable breeze, smooth sea, slight swell, showery; vessel lying quietly. (See issue of Apr. 12.)

AYRSHIRE.—London, Apr. 13. — The owners of steamer Ayrshire have received the following messages from the vessel:

Timed 8 20 a.m., Apr. 11: Engine-room no change. Steamer Ais Nicolas alongside 8 a.m., clearing heavy lifts from No. 2 and No. 2 'tween decks. Light NE. wind, slight swell. All well.

Timed 8 a.m., Apr. 12: Engine-room no change, but slight increase tunnel leakage, not serious. Continue to discharge cargo Nos. 2 and 4 'tween decks. Morale and health good. Wind light NE., slight swell. (See issue of Apr. 13.)

London, Apr. 13. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 12: Position of vessel unchanged. Discharging from Nos. 2 and 4 holds continued into steamer Ais Nicolas. Weather variable, sea smooth; vessel quiet.

smooth, vessel quiet. London, Apr. 13. — The owners of steamer Ayrshire have received the following message from the vessel, timed 8 a.m., Apr. 13: No change in engine-room. Expect salvors endeavour refloat Thursday-Friday (Apr. 15-16). No. 4 port wing tank contaminated and filling slowly. Fresh water position can be maintained by rationing. Weather light, SE. wind, slight swell.

AYRSHIRE. — London, Apr. 14. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 13: Position unchanged. Discharging continued from Nos. 3 and 5 'tween decks into steamer Ais Nicolas and present indications point to refloating Apr. 15 or 16. Weather fine and vessel quiet. (See issue of Apr. 14.)

AYRSHIRE. — London, Apr. 15. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 14: No appreciable change in position. Discharging continued from No. 5 'tween deck to steamer Ais Nicolas. Pumps positioned and being tested. Moderate south-easterly weather, slight sea and swell, vessel quiet. (See issue of Apr. 15.)

AYRSHIRE. — London, Apr. 17.—The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire:

Dated Apr. 15: Position unchanged. Continued discharging No. 5 lower hold and at 5 p.m. to-day total tonnage transhipped approximately 900 tons and jettisoned 623 tons. Refloating trial to-morrow. Weather south-easterly wind of force 4 (moderate breeze), slight sea and swell, vessel lying quietly.

Dated Apr. 16: To-day's refloating trial abandoned at nightfall. Progress in No. 2 hold moderate, No. 3 good, No. 4 poor. Rearrangement of pumps being made for to-morrow's attempt. Steamer Ais Nicolas anchored offshore. Weather south-easterly wind of force 4, slight sea and swell, vessel lively after pumping. (See issue of Apr. 17.)

AYRSHIRE.—London, Apr. 20.—The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire:

Dated Apr. 17: Refloating trial unsuccessful as effective pumping capacity not sufficient. Consider that unless salvors quickly provide much greater efficient pumping resources vessel will become constructive total loss. Weather remains favourable but must stress utmost urgency. There remains 700 tons readily accessible sound cargo and

Amstelslot, Amsterdam, Wilthy & Co
Caindgowan, Montreal, Imperial, Furness, W
Dryburgh, Antwerp, Albert, G. Gibson & Co
Ettick, Rotterdam, Albert, G. Gibson & Co
Heriot, Amsterdam, Albert, G. Gibson & Co
readily accessible and cargo

Apr	Benvenue, Hong Kong, Buchan & Hoeg.
Apr	Heriot, Amsterdam, Rahnke & Salvesen.
Apr	Ivan Mazurait, Rileke, Grange, Currrie Line.
Apr	Ness, Umea, J. T. Salvesen & Co.
Apr	Pendland, Amsterdam, Furness Withy & Co.
Apr	Ploner, Amsterdam, Grange, Currrie Line.
Apr	Tells, Kotka, Grange, Currrie Line.

BURNT ISLAND
Activity, Takoradi, Dewar & Lawson, Apr

GRANGEMOUTH
Amsterdam, Furness, Wily & Co Apr

11/4/65

AYRSHIRE.—London, Apr. 1.—The owners of steamer Ayrshire have received the following message from the master, dated Apr. 1: Condition of engine-room still deteriorating. Location frame 91 port inboard main girder bracket connection to tank top buckled, starboard inboard bracket tank top fractured and rivets in locality leaking. Location frame 80 starboard main girder buckled, port main girder rivets in connection between girder and lower deck stringer sheared. Location frame 75 tank top connection to main girder buckled. Water in Nos. 2 and 3 being held at very low level. Insufficient pump capacity to reduce water level in No. 4 hold. Night and morning attempts to tow off unsuccessful. Two hundred and fifty tons of oil fuel discharged overboard from side bunkers overnight has eased weight in way of engine-room. Discharging all fuel from cross and side bunkers. One hundred tons of cargo jettisoned No. 1 hatch. Rigging salvage anchor to assist this evening attempt to tow off. Morale and health of personnel excellent. (See issue of Apr. 1.)

Aden, Apr. 1.—Steamer Ayrshire: Tug Poolzee arrived here on Mar. 31 and left the same day.

12/4/65

AYRSHIRE.—London, Apr. 2.—The owners of steamer Ayrshire have received the following message from the master, dated Apr. 2: Height of water above tank tops No. 2 12 ft. 9 in., No. 3 6 ft., No. 4 18 ft. 6 in. Depth of water alongside forward 23 ft., amidships starboard 25 ft., port 22 ft., aft starboard quarter 30 ft., port quarter 29 ft., right aft 30 ft. Two additional pumps received from tug Noordzee now installed in No. 4 hold. Consider lowering level of water in No. 4 to be best pending arrival of Colthoff and salvage party, which expect to-night. Calculated GM 2 ft. 7 in. draught 21 ft. 4 in. forward, 31 ft. 4 in. aft under present condition. Effort to refloat last night abandoned as salvage anchor would not hold. Weather conditions: Moderate wind on port beam; slight swell develops during day and moderates at night. (See issue of Apr. 2.)

13/4/65

AYRSHIRE.—London, Apr. 3.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 2: Tug Poolzee party arrived Ayrshire at 5 p.m., G.M.T., also motor coaster Seiyun. (See issue of Apr. 3.)

14/4/65

AYRSHIRE.—London, Apr. 3.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 3: Salvors advise five six-inch and five three-inch pumps being dispatched by air to Aden on Apr. 5. Divers' examination of starboard side to-day shows vessel resting on rock and sand from forward to after end of No. 5 hold. Pumping presently being regulated to keep vessel solidly aground. Steamer Ais Nicolas to lighter majority of remainder of sound cargo; meantime, discharging continued from Nos. 2 and 3 shelter decks into motor coaster Seiyun. Weather south-easterly, force 4 (moderate breeze), slight sea and swell. Vessel lying quietly. (See issue of Apr. 5.)

London, Apr. 5.—The owners of steamer Ayrshire have received the following message from the master, timed 5 24 p.m., Apr. 3: Divers' examination starboard side vessel resting evenly on rock and sand from forward to No. 5 hatchway, aft of which unsupported. Salvors advise 10 extra pumps being flown chartered aircraft Rotterdam-Aden early next week; instruct master of motor vessel Clan Maclean on-carry and rendezvous here with tug. Meantime, pumping suspended Nos. 2 and 4 to retain vessel in present firm position. Vessel still lying comfortably. Discharge of cargo into coaster from Nos. 2 and 3 shelter decks nearly complete, start No. 4 shelter deck tomorrow. Steamer Ais Nicolas, 6,000 tons deadweight, estimated date of arrival Wednesday (Apr. 7) for discharge balance undamaged cargo, excluding heavy lifts.

London, Apr. 5.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 4: Continued discharging from shelter and 'tween decks into motor vessel Seiyun. Salvors working on

bottom damage where accessible. Weather south-easterly, force 4 (moderate breeze), slight sea and swell. Vessel lying quietly.

11/4/65
AYRSHIRE.—London, Apr. 6.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 5: Discharging continued from upper decks into motor vessel Seiyun, which completed and sailed for Aden at 1 p.m. Salvors continued work on bottom damage. Jettisoning chemicals from Nos. 1 and 6 and egg fillers from No. 2. Weather south-easterly, force 3 (gentle breeze), slight sea and swell. Vessel lying quietly. (See issue of Apr. 6.)

12/4/65

AYRSHIRE.—London, Apr. 7.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 6: Double bottom tanks No. 4 starboard centre, No. 4 port centre and No. 5 port all found to be contaminated by salt water this morning, otherwise hull position unchanged. Waterlogged oil-stained bales jettisoned from No. 3 and paper sacks of calcium carbonate from No. 6 hold. Weather south-easterly, force 3 (gentle breeze), slight sea, swell slightly increased. Vessel lying quietly. Lighter steamer Ais Nicolas expected to depart from Aden for Ayrshire on Apr. 7. Aden agents report. (See issue of Apr. 7.)

London, Apr. 7.—The owners of steamer Ayrshire have received the following messages from the master:

Timed 8 18 a.m., Apr. 6: Condition of engine-room unchanged. No. 4 double bottom port and starboard inner tanks and No. 5 double bottom port and starboard common to sea. Fresh-water pressure system discontinued. Rationing from peaks. Steamer Ais Nicolas delayed repaired Aden. Cory (owners' agents at Aden) advise steamer Nunzia may be available. Stop jettison further cargo owing to possibility of fouling access alongside. Urgently require coaster for lightening.

Timed 8 a.m., Apr. 7: Condition of engine-room still unchanged. No definite news Ais Nicolas. Nunzia definitely not available. To-day's amended cargo distribution No. 5 upper 'tween deck 90 tons, No. 6 lower hold 220 tons. Morale and health remain good. Weather light SE. wind, slight swell.

13/4/65

AYRSHIRE.—London, Apr. 8.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 7: Continued jettisoning paper sacks lime from No. 6 hold. Weather light airs, smooth sea, long low swell. Vessel lying quietly. (See issue of Apr. 8.)

14/4/65

AYRSHIRE.—London, Apr. 9.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 8: Position unchanged. Vessel lying quietly. Further jettisoning of bricks from No. 4 'tween deck carried out. Steamer Ais Nicolas left Aden at 8 15 a.m., G.M.T., to-day and is due here in morning of Apr. 10. Weather light variable winds, smooth sea, light swell. (See issue of Apr. 9.)

London, Apr. 9.—Steamer Ayrshire: The owners' agents at Aden advise: Steamer Ais Nicolas sailed at 11 45 a.m., Apr. 8, with engineers pumps machines on board, estimated time of arrival at Ayrshire 6 a.m., Apr. 10.

15/4/65

AYRSHIRE.—London, Apr. 10.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 9: Position materially unaltered. Continued jettisoning bricks from Nos. 1 and 4 'tween decks and preparing cargo for transfer to steamer Ais Nicolas, whose arrival now reported morning of Apr. 11. Weather light airs, smooth sea, slight swell; vessel quiet. (See issue of Apr. 10.)

16/4/65

AYRSHIRE.—London, Apr. 12.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 10: Position remains unchanged. Completed jettisoning pallets firebricks from No. 1 'tween deck. Remaining holds ready for discharge into lighter steamer, which now due 2 a.m., G.M.T., Apr. 11. Light variable breeze, smooth sea, slight swell, showery; vessel lying quietly. (See issue of Apr. 12.)

11/4/65

AYRSHIRE.—London, Apr. 13.—The owners of steamer Ayrshire have received the following messages from the vessel:

Timed 8 20 a.m., Apr. 11: Engine-room no change. Steamer Ais Nicolas alongside 8 a.m., clearing heavy lifts from No. 2 and No. 2 'tween decks. Light NE. wind, slight swell. All well.

Timed 8 a.m., Apr. 12: Engine-room no change, but slight increase tunnel leakage, not serious. Continue to discharge cargo Nos. 2 and 4 'tween decks. Morale and health good. Wind light NE., slight swell. (See issue of Apr. 13.)

London, Apr. 13.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 12: Position of vessel unchanged. Discharging from Nos. 2 and 4 holds continued into steamer Ais Nicolas. Weather variable, sea smooth; vessel quiet.

London, Apr. 13.—The owners of steamer Ayrshire have received the following message from the vessel, timed 8 a.m., Apr. 13: No change in engine-room. Expect salvors endeavour refloat Thursday-Friday (Apr. 15-16). No. 4 port wing tank contaminated and filling slowly. Fresh water position can be maintained by rationing. Weather light, SE. wind, slight swell.

15/4/65

AYRSHIRE.—London, Apr. 14.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 13: Position unchanged. Discharging continued from Nos. 3 and 5 'tween decks into steamer Ais Nicolas and present indications point to refloating Apr. 15 or 16. Weather fine and vessel quiet. (See issue of Apr. 14.)

16/4/65

AYRSHIRE.—London, Apr. 15.—The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 14: No appreciable change in position. Discharging continued from No. 5 'tween deck to steamer Ais Nicolas. Pumps positioned and being tested. Moderate south-easterly weather, slight sea and swell, vessel quiet. (See issue of Apr. 15.)

17/4/65

AYRSHIRE.—London, Apr. 17.—The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire:

Dated Apr. 15: Position unchanged. Continued discharging No. 5 lower hold and at 5 p.m. to-day total tonnage transhipped approximately 900 tons and jettisoned 623 tons. Refloating trial to-morrow. Weather south-easterly wind of force 4 (moderate breeze), slight sea and swell, vessel lying quietly.

Dated Apr. 16: To-day's refloating trial abandoned at nightfall. Progress in No. 2 hold moderate, No. 3 good, No. 4 poor. Rearrangement of pumps being made for to-morrow's attempt. Steamer Ais Nicolas anchored offshore. Weather south-easterly wind of force 4, slight sea and swell, vessel lively after pumping. (See issue of Apr. 17.)

18/4/65

AYRSHIRE.—London, Apr. 20.—The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire:

Dated Apr. 17: Refloating trial unsuccessful as effective pumping capacity not sufficient. Consider that unless salvors quickly provide much greater efficient pumping resources vessel will become constructive total loss. Weather remains favourable but must stress utmost urgency. There remains 700 tons readily accessible sound cargo and coaster could be profitably employed Vacuum tower; preparations are in hand for discharge, probably Apr. 19.

Dated Apr. 19: Position unchanged. Vacuum tower discharged and is now under tow to Aden by tug Poolzee. Towing arrangements satisfactory and vacuum tower apparently of good stability and floating at about 34-ft. draught. Chocks and slings sent Aden per tug Oceana, which will return with five 6-in. pumps flown from Rotterdam. Tug Mississippi, now in attendance, has one 6-in. pump, one 4-in. pump and four 3-in. pumps. Continued jettisoning naphthalene No. 1 lower hold 1,500 bags, marked "R.C.I." over "E Sydney," have also decanted 29½ tons bulk Dutrea 55, mark "Shell Chemical Company Australia" and 29 tons bulk naphthenic acid, same consignees, into sea, both carried in portable deck tanks. Salvage crew overhauling and placing pumps. Vessel lying quietly. Wind south-easterly, force 3 (gentle breeze), slight sea and long low swell. (See issue of Apr. 19.)

Aden, Apr. 19.—Steamer Ayrshire: Approximately 700 tons of cargo arrived per steamer Ais Nicolas noon, Apr. 19.

London, Apr. 20.—The owners of steamer Ayrshire have received the following message from the master, dated Apr. 20: Condition of engine-room unchanged. Motor vessel Clan Matheson taken mail and supplied stores; proceeded on voyage at 7 a.m., G.M.T. Continue discharge No. 1. Seventy tons remain. Some water on tank top, not serious; no appreciable change in soundings. Cargo distribution this morning in tons No. 1 70, No. 2 495, No. 3 663, No. 4 548, No. 5 300, No. 6 243, deck 10 only. Coaster expected Thursday (Apr. 22); will discharge from Nos. 5 and 6. All well.

12 2/3

227/4/65
AYRSHIRE. — London, Apr. 21. — The owners of steamer Ayrshire have received the following message from the master, timed 8 20 a.m., Apr. 21: Condition of engine-room unchanged. Water in No. 1 lower hold about 2 ft., little change. Fresh SSE. wind; swell has increased but still slight. (See issue of Apr. 21.)

223/4/65
AYRSHIRE. — London, Apr. 22. — The owners of steamer Ayrshire have received the following message from the master, timed 8 a.m., Apr. 22: Condition of engine-room unchanged. Fresh SE. wind; swell increased, now about 3 ft., southerly. (See issue of Apr. 22.)

Aden, Apr. 22. — Steamer Ayrshire: Tug Oceaan arrived here on Apr. 21.

224/4/65
AYRSHIRE. — London, Apr. 23. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 22: No change in condition of vessel, which moving slightly. Fresh south-south-easterly wind, moderate sea swell. Time of utmost importance. Pumps reported due Aden to-night. Coaster not arrived. (See issue of Apr. 23.)

London, Apr. 23. — Steamer Ayrshire: The Salvage Association have received the following telephonic advices from Messrs. L. Smit & Company's salvage officer at Rotterdam: "Ayrshire: Six six-inch pumps arrived Aden and were placed on tug Oceaan, which left Aden for casualty at 2 30 a.m., Apr. 23. Present intention is to keep casualty on ground until Saturday morning (Apr. 24), when Oceaan due with pumps, then, with the additional pumping capacity, to float vessel and move her half a ship's length for examination as to ability to cope with ingress of water. If satisfactory, vessel to be moved into a lee position at Cape Guardafui. Divers are in attendance; have done some tightening in engine-room and No. 2. No. 4 hold is unpumpable and presently inaccessible for tightening. A 400-ton coaster is due alongside this morning to take further cargo off vessel; 700 tons approximately now remain on board. Tug Poolzee delivered cracking tower to Aden and is now en route to casualty. Pumps available by Saturday 11 six-inch, three four-inch and 17 three-inch, plus one eight-inch and one three-inch which salvors hired from Aden." The Association have stressed urgency for effective action on this vessel as SW. monsoons imminent.

London, Apr. 23. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 23: Position unchanged. No apparent buckling of any shell or deck plating although bottom seriously damaged for practically whole length. Nos. 1, 5 and 6 holds dry, engine-room easily contained. Movement slight. Salvors say they are not prepared to attempt salvage in present weather conditions, which south-south-east, force 4 (moderate breeze), and moderate sea and swell, but if no attempt is made there can be only one possible result. Motor coaster Shibam arrived and now lying alongside quietly, receiving cargo from Nos. 4 and 5 holds. H.M. destroyer Cambrian keeping in vicinity for next four days.

227/4/65
AYRSHIRE. — London, Apr. 23. — Steamer Ayrshire: The Salvage Association have received the following telephonic advices from Messrs. L. Smit & Company's salvage officer at Rotterdam: "Ayrshire: Six six-inch pumps arrived Aden and were placed on tug Oceaan, which left Aden for casualty at 2 30 a.m., Apr. 23. Present intention is to keep casualty on ground until Saturday morning (Apr. 24), when Oceaan due with pumps, then, with the additional pumping capacity, to float vessel and move her half a ship's length for examination as to ability to cope with ingress of water. If satisfactory, vessel to be moved into a lee position at Cape Guardafui. Divers are in attendance; have done some tightening in engine-room and No. 2. No. 4 hold is unpumpable and presently inaccessible for tightening. A 400-ton coaster is due alongside this morning to take further cargo off vessel; 700 tons approximately accessible sound cargo now remains on board. Tug Poolzee delivered cracking tower to Aden and is now en route to casualty. Pumps available by Saturday 11 six-inch, three four-inch and 17 three-inch, plus one eight-inch and one three-inch which salvors hired from Aden." The Association have stressed urgency for effective action on this vessel as SW. monsoons imminent. (Not as reported in issue of Apr. 24.)

London, Apr. 26. — The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire, dated Apr. 25:

(1) Condition unchanged. Continued discharge from Nos. 5 and 6 holds into motor vessel Shibam. Weather fine, calm sea. Tug Oceaan with pumps due to-night, install to-morrow. Hopeful refloating attempt Apr. 26.

(2) Carried out refloating attempt to-day without success. Rearranging pumps for to-morrow's attempt. Pumping effort satisfactory, but pumps choked with much debris in lower part of holds and vessel rolling and bumping during pumping. Weather fine, sea smooth. Shibam sailed for Aden at 8 15 p.m., Apr. 24, with approximately 290 tons.

London, Apr. 26. — The owners of steamer Ayrshire advise receiving the following messages from the master:

Timed 4 p.m., Apr. 25: To-day's effort unsuccessful but indicated aground just aft of amidships. Salvors now rearranging pumps in endeavour to lower water in No. 4. Pumping commenced at 10 a.m., G.M.T., and from about noon there was appreciable rolling and some pitching. Maximum ullages achieved from tween deck plating No. 2 16 ft. 8 in., No. 3 12 ft. 5 in. During latter stage, pumping greatly impaired by frequent chokeage of suction strainers by decomposed paper and packing from cargo. Anticipate another endeavour to-morrow. To-day's effort caused no concern regarding stability.

Timed 8 15 a.m., Apr. 26: Condition of engine-room unchanged. Pumping recommenced at 6 30 a.m., G.M.T. Ship shifted six feet inshore during night. Weather continues fine. All well on board.

228/4/65
AYRSHIRE. — London, Apr. 27. — The owners of steamer Ayrshire have received the following message from the master, timed 5 p.m., Apr. 26: Vessel refloated at 1 20 p.m., G.M.T.; 21 ft. 6 in. forward, 22 ft. 9 in. aft, ample stability. Vessel towed approximately one ship's length astern into deeper water when, with starboard anchor down, one tug fast aft, one tug at anchor and one tug stationary alongside, vessel swung ashore. Now fast and bumping heavily, with ship's head east, parallel to shore. Position now greatly deteriorated. Engine-room remaining intact; provision made to transfer diesel oil into oil fuel settling tanks. All well and cheerful. Weather still excellent. (See issue of Apr. 27.)

London, Apr. 27. — The Salvage Association have received the following radio messages from their salvage officer on board steamer Ayrshire:

Dated Apr. 26: After successful refloating at 1 20 p.m., G.M.T., to-day, vessel drifted ashore on west side Bandar Saleh, Abd-al-Kuri, and is now in grave danger of becoming unsalvageable as position much more exposed and vessel's after body bumping heavily. Tugs Mississippi and Oceaan fast aft but so far have failed to improve conditions and, as most water has now been pumped out, there is not much that can be done to lighten aftership.

Dated Apr. 27: Tugs' efforts last 12 hours unavailing and position of utmost seriousness as two-knot current pinning ship on reef and vessel bumping and labouring, with some evidence of deterioration. No. 6 tank now leaking. No. 1 hold actively leaking and engine-room leakage increased slightly. Understand salvors now considering abandonment and, if so, crew will be removed. Weather continues fine, light breeze, smooth sea, slight swell.

Dated Apr. 27: Salvors making no further active effort to refloat apart from continuation of towing with two tugs from starboard quarter. As they now disconnecting pumps preparatory to removal and as vessel is heavily grounded, with most of available lifting capacity already utilised, consider no possibility of salvage in time remaining before onset of monsoon.

Rotterdam, Apr. 27. — Steamer Ayrshire: Our salvage inspectors reported this morning that situation deteriorated to such an extent that they were forced to abandon further salvage operation of the Ayrshire.—L. Smit & Co.

229/4/65
AYRSHIRE. — London, Apr. 28. — The Salvage Association have received the following radio message from their salvage officer on board steamer Ayrshire, dated Apr. 28: Tugs Poolzee and Mississippi left for Aden with part salvors and Ayrshire personnel. Am informed tug Oceaan will finally leave with remaining personnel at noon, G.M.T. (See issue of Apr. 28.)

230/4/65
AYRSHIRE. — Aden, Apr. 28. — Steamer Ayrshire: Understand from local agents that Ayrshire abandoned. — Lloyd's Agents per Salvage Association. (See issue of Apr. 29.)

Rotterdam, Apr. 29. — The Dutch salvage firm of L. Smit & Co. said in Rotterdam to-day that steamer Ayrshire cannot be saved. The salvage company said its men worked for more than a month to get the ship afloat. On Apr. 26, she floated for eight minutes but was caught by a strong current and grounded again. Smit's reported that the ship's cargo was recovered. The company used three tugs and 34 salvage pumps in the attempt.—British United Press.

215/65
AYRSHIRE. — London, Apr. 30. — Steamer Ayrshire: It was stated erroneously that L. Smit & Co. had reported that the ship's cargo was recovered. L. Smit & Co. said that 1,400 tons of cargo was safely brought into Aden and that a valuable cracking tower, badly needed by a refinery in Australia, was saved and later taken on board another ship for Brisbane.—British United Press. (See issue of Apr. 30.)

London, Apr. 30. — Steamer Ayrshire: The Salvage Association is inquiring whether any other salvors are interested in undertaking salvage operations. Salvage vessel Svitser, presently en route to Aden, will undertake a survey of the Ayrshire providing she is not diverted to another casualty in the meantime. Replies from other contractors are awaited.