

For Mr. Ward, Wok.

"EMPIRE SCOTT"


Messrs. John Readhead & Sons' No. 523

Rule Dimensions:- 400' x 53.29' x 35.87' to up.dk.

Class:- 100A1 "With freeboard".

in view of e.s.s. used with T.O.

The scantlings are such that with the tonnage opening closed a freeboard corresponding to an increased draught of 18" can be assigned. As in other vessels building for the Admiralty, the watertight bulkheads have been extended to the upper deck, with the scantlings of the hold bulkheads based on a height to the second deck. A reduced length of cable accepted, and the third bower anchor omitted. No exception was taken to the omission of the forecastle, if desired.


15th September, 1941.



© 2020

Lloyd's Register
Foundation

004285-004291-0044