

Lloyd's Register of Shipping.

Ship's Name S.S. DAY-Y-BRYNOfficial No. 167382

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in ANTWERP 14th JUNE 1946.

1. The tonnage opening in the shelterdeck has been restored and closed by efficient temporary covers.
2. All openings in the tonnage well bulkheads have been closed as required for full allowance.
3. All scuppers which are led to the hold bilges from the shelter tween decks have been permanently closed.
4. Drain holes have been cut in the wings of the forecastle deck bulkheads to permit of the drainage of water to the machinery space bilge.
5. An overboard scupper of 5" in diameter has been fitted on each side of the tonnage well with a screw down automatic non return valve controlled from the shelter deck and having an indicator showing whether the valve is open or closed.

Affidaventur

