

# Lloyd's Register of Shipping.

Ship's Name *S.S. DAN-Y. BRYN*Official No. *167382*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in *ANTWERP 14<sup>th</sup> JUNE 1946*

1. *The tonnage opening in the shelterdeck has been restored and closed by efficient temporary covers.*
2. *All openings in the tonnage well bulkheads have been closed as required for full allowance.*
3. *All scuppers which are led to the hold bilges from the shelter tween decks have been permanently closed.*
4. *Drain holes have been cut in the wings of the tween deck bulkheads to permit of the drainage of water to the machinery space bilge.*
5. *An overboard scupper of 5" in diameter has been fitted on each side of the tonnage well with a screw down automatic non return valve controlled from the shelter deck and having an indicator showing whether the valve is open or closed.*

*V. H. H. H. H.*

Nota  
Am.  
2. IX. 46