

SHIP'S NAME SAFINA-E-JAMHORIYATLIV. - - - - - 168260.
PORT ANT. No. 42037.

11.2.66+ LAST SURVEY DATE 31.3.66.

CLASS IS SUBJECT TO

- 1 M/E. L.P. unit and its alignment be further examined and dealt with as found necessary by 5.66.
- 2 Attached Port Sidel Pump water cylinder valve chest flange being examined and dealt with as found necessary by 3.67 (12 mos)
- 3 Starboard boiler is not to be used until repairs to Butt strap are satisfactorily completed.

SAH item NO1:- now dealt with & submitted be deleted from SA list.

SAH item NO2:- Starboard Boiler examined internally & externally in way of butt strap leakage. Three rivets removed, the rivet holes crack detected by magna flux method & no signs of cracks could be found. New rivets of Lloyd's tested material fitted.

The butt strap top edge in way of leakage cut back as shown on attached sketch and caulked internally & externally.

On Completion of repairs Boiler tested hydraulically and found tight.
Submitted this item be deleted from SA list.

Antwerp Surveyor should be asked to confirm in writing that the subject re Starboard boiler imposed by Dundee Surveyor should now be deleted.

It is submitted that this vessel is eligible to remain as CLASSED 21

Subject as above for item NO 2 but without special conditions for items 1 & 3.

Note date of Survey of Liv Report 168260 which was previous to both Dundee & Antwerp Surveys & receipt of Report in this office.

004405-004410-085