

Ship's name "SAFINA - E - JAMHOORIYAT"

Port N.N.S.

No. 8790.

Class is subject to

⁴
13.10.64 Last survey date 7.10.64.

- 1 Exhaust Steam Turbine being repaired & re-installed by 2.65 (6 mos)
- 2 the seal-welded stay tabs in Centre Box of Starboard boiler being renewed at next MBS.

Steering engine crankshaft journals found heavily pitted & scored & the coupling driving Hel-shaw pump slack.

Crankshaft journals lapped in place & bearings adjusted, new key fitted to Hel-shaw pump coupling

It is recommended that steering engine crankshaft & pump coupling being further examined and dealt with as found necessary by end of December 1964.

It is submitted that this vessel is eligible to remain as CLASSED.

Subject as above and as now recommended.

Lloyd's Register
Foundation

11.11.64.