

GREENOCK DOCKYARD CO.LTD.

No. 454

PARTICULARS OF AIR COOLERS

<u>Space</u>	<u>No. & Type</u>	<u>No. of Brine Coil Sections</u>
No. 2 Upper Tween Deck	1 Twin	10
No. 2 Lower Tween Deck	1 Twin	10
No. 2 Hold	1 Twin	14
No. 3 Upper Tween Deck	1 Twin	6
No. 3 Lower Tween Deck	2 Single	3 each
	1 Twin	4
No. 3 Hold	1 Twin	6
No. 4 Upper Tween Deck	1 Twin	6
No. 4 Lower Tween Deck	2 Single	2 each
	1 Twin	4
No. 4 Hold	1 Twin	4
No. 5 Upper Tween Deck	1 Twin	8
No. 5 Lower Tween Deck	2 Single	3 each
	1 Twin	4
No. 5 Hold	1 Twin	6

N.B. Nos. 3, 4 & 5 Lower Tween Deck spaces will be sub-divided at some future date when each sub-division will have a separate cooler.

AIR CIRCULATING FANS

<u>No. off</u>	<u>Size</u>	<u>Capacity - C.ft per min. each</u>	<u>R.P.M. Max.</u>
2	24"	8500	2220
6	25"	8500	1930
10	27½"	12500	1980
4	32½"	15000	1580
2	45"	29000	1040

© 2021

Lloyd's Register
Foundation

004662-004667-0129