

LONDON COPY.

Messrs. Barclay Curle & Co. Ltd.,
Clydeholm shipyard,
Whiteinch, Glasgow, W.4.

1st Sept., 47.
3873.

OUTLINE SPECIFICATION OF COOLING APPLIANCES TO BE PROVIDED FOR TWO ADDITIONAL CARGO CHAMBERS.

"SANGOLA". 707

General.

The two future chambers foreseen in the original specification are now to be fitted. Our contract covers for the provision of the necessary cooling appliances and piping for leads; the whole packed for shipment and delivered f.o.b. London. Erection will be carried out in India, we believe, Calcutta.

The new chambers will be immediately abaft of the existing port and starboard ~~xxxx~~ spaces and each room will have a capacity of around 2500 cu.ft.

We are to supply to Lloyd's, fees not paid by J. & E. Hall, Ltd.:-

Symbol A - Tachometers.

Two tachometers arranged for fitting on the machine bases and to be belt-driven from the existing half couplings.

Symbol M - Grids.

A set of galvanised brine grids arranged for installation on the sides and overhead, the former having galvanised channel iron supports and the latter, galvanised clip supports, to enable the grids to be screened for air circulation.

We are to provide for each chamber approximately 750 ft. run on the roof and 850 ft. run on the sides.

Symbol R - Brine Service Pipes.

The requisite 1½" bore externally galvanised brine service piping for coupling up between the existing brine leads and the new cooling circuits. The piping to be shipped in random straight lengths for bending at site.

Symbol S - Fans.

Two horizontal extended spindle fans of Messrs. Woods' manufacture, each to circulate 2500 c.f.m. against 1½" S.G.

The fans to be complete with totally enclosed motors and Bray starters, identical with the gear originally supplied for the Starboard Cargo Chamber.

Symbol U - Spare Gear.

The fans being identical with the units already fitted, the only spare gear to be supplied will be -

2 sets of carbon brushes.

004698-004702-02981/2

1.9.47.

Messrs. Barclay Curle & Co. Ltd.

Order No. 3873.Outline Specification (Cont.)Symbol X - Drawings.

Drawings and alterations to patterns, including the provision of erection drawings in duplicate for the Builders to forward to India.

Symbol Y - Delivery.

Packing as required for overseas shipment and delivery f.o.b. London.

Despatch to be effected in March 1948.

The remaining requirements of the Rules for Refrigerating Machinery & Appliances to be complied with so far as they are applicable.

MRH

7.10.47.

LONDON COPY.



© 2021

0298212
Lloyd's Register
Foundation