

004755-004760-0250

PORT on the Messers Chantier de Penhoet. S. Nazaire. M.V. No 15.

It is submitted the freeboards given on the accompanying form being those required by the Tables merit approval, the same to be marked on the vessel's sides, inserted in the certificate of classification, and recorded in the Register Book, subject to the particulars and dimensions now supplied being verified on completion of the ship, to the usual covers being fitted to the openings in the steel tween deck bulkheads in way of the tonnage opening and to efficient temporary covers being provided for closing the tonnage opening on Superstructure Deck.

The freeboards have been computed on a corrected tonnage coefficient of .74 and are subject to alteration if found necessary.

When submitting his final report the Surveyor should give particulars of the freeing ports situated in the tonnage well and state whether non-return valves are fitted to the overboard scuppers from the tween decks

9-11-26 S.W.B.

Length.

Length allowed.

Height.

Correction necessary because clearside amidships measured