

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH  
AT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR  
GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS  
CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Newport Mon  
Date of Survey 19.7.32.  
Name of Surveyor

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
<u>VENTLAND</u>	<u>Newport Mon</u> <u>British</u>	<u>145645</u>	<u>1821</u>	<u>1923-7</u>	<u>+100A1</u>
Number in Register Book					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	<u>264.0</u>	<u>39.0</u>	<u>17.0</u>	<u>1404</u>
Length on LOADLINE.	<u>264.0</u>	Frame <sup>mean</sup> Depth <sup>8</sup> Rule <sup>" 5</sup> <sub>2 x 3</sub> <u>= - .5</u>	Ceiling <sup>fitting</sup> Sheer <u>4.50</u>	Peak Tanks } <u>Inclu</u>
CORRECTED DIMENSIONS.	<u>264.0</u>	<u>38.5</u>	<u>17.5</u>	<u>1404</u>

Co-efficient of fineness..... .79  
Any modification necessary }  
[Para. 4 (a) to (e)]\* } .02 CAB.  
Co-efficient as corrected ..... .77

Sheer { Stem..... 72 } 108 ÷ 2 = 54 ...Mean 54.54  
at { Sternpost ... 36 } 36.40  
36.14  
.50  
Sheer at  $\frac{1}{8}$  of the length from { Stem 40 } 60 ÷ 2 = 30 ...Mean  
{ Sternpost 20 } 54.54  
Gradual mean Sheer ..... 54.54 + 54 ..... = 54.27 ÷ 55 = 54.54  
Standard mean Sheer [Table, Para. 18] ..... 36.40 Correction  
Difference..... 17.87 ÷ 4 = 4.47  
§ If limited as Para. 18 (f) ..... - 4.47

Rise in Sheer { At front of bridge house.....  
from amidships {  
[Para. 18 (e)] { At after end of forecastle .....

Fall in Sheer }  
Para. 18 (d) } ÷ 2 =  
Length uncovered ..... Correction

### ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... 1-3  
Correction for Length, if required (Para. 12, 13, and 14) .....  
Freeboard by Table A, corrected for sheer, and for length, } 3-4 1/4  
if required (Para. 11, 12, 13, and 14) }  
Difference ..... 2-1 1/4  
Percentage as below..... 55.75%  
14.1

Correction for R. Q. Dk. if engine and boiler openings not }  
covered by bridge house (Para. 11) }  
Allowance for Deck Erections ..... - 14  
Length. <sup>Inclu 9"</sup> Length allowed. Height.  
Forecastle..... 24-5 1/2 } 25.20 7.0  
Bridge House ..... 56-9 1/2 } 58.04 7.0  
† Raised Qr. Dk..... 102-5 1/2 } 97.88 4.0  
Poop..... 77-2 } 5.07  
38.3 25.25 1.24 4.66 x 8 + 2  
Total ..... 186.19 = .705  
Length of Ship ..... 264  
Corresponding percentage }  
(Para. 11, 12, 13, or 14) } 55.75%

Moulded Depth as measured..... 19-5 1/2  
Addition for Keel below base line  
for draught record..... 1 1/4 inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

### CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 264.0  
Length in Table ..... 233.0  
Difference ..... 30.5  
Correction for 10ft., Table A. .... 1.1 Table C.  
× Difference divided by 10 ..... 3.355 (if required.)  
If  $\frac{1}{10}$ ths length covered divide by 2 1.677 + 1 3/4

### CORRECTION FOR IRON DECK.

Proportion covered, if less than  $\frac{1}{10}$ ths length covered ..... .695  
Thickness of usual wood deck, less stringer ..... 3 1/2 = - 3 1/2

### CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 38-0  
Round of Beam ..... 9  
Normal round..... 9 1/2  
Difference ..... 1/2 ÷ 2 = ..... 1/4  
Proportion of Deck uncovered (Para. 19) ..... ✓

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A ..... 3-8 3/4  
Correction for Sheer ..... 4 1/2  
3-4 1/4  
Correction for Length ..... 1 3/4  
3-6  
Allowance for Deck Erections ..... 1-2  
2-4  
Correction for Round of Beam..... ✓  
Correction for fall in Sheer (if any)..... ✓  
Correction for Steel Deck (if required) ..... - 3 1/2  
2-0 1/2  
Additions for non-compliance with provisions of }  
Para. 11 (d) and (e) † } ✓  
Other Corrections (if any) ..... ✓

Winter Freeboard ..... 2-0 1/2  
Summer Freeboard ..... 3 1-9 1/2  
Indian Summer Freeboard ..... 1-6 1/2  
N. A. Winter Freeboard ..... 2-3

Correction necessary because clearside amidships, measured }  
in accordance with the Statute is not taken at the }  
intersection of the wood or steel deck with side.

Winter Freeboard from deck line .....  
Summer " " " " .....  
Indian Summer " " " " .....  
N. A. Winter " " " " .....

### SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ... 8 Tropical Fresh Water Freeboard ... 1-1 1/4  
Fresh Water Line " " ... 5 Fresh Water " " ... 1-4 1/4  
Tropical Line " " ... 3 Tropical " " ... 1-6 1/4  
Winter Line below " " ... 3 Winter " " ... 2-0 1/4  
Winter North Atlantic Line " " ... 5 Winter North Atlantic " " ... 2-2 1/4

14 SEP 1932