



Lloyd's Register of Shipping

231 St. James Street West,

Montreal.

RECEIVED

14th November, 1945

1 - DEC 1945

Reference
S.

The Secretary
LONDON

ANSD.....

Dear Sir;-

In reply to the Classing Letter dated the 23rd October, 1945, we have to advise as follows;-

Montreal Report No. 6652 "CABEDELLO"

- (1) It is confirmed that single riveting in the seams of the bridge side plating was approved, but the seam connecting bridge side plating to upper deck sheer strake is double riveted.
- (2) The double bottom tank under the boilers is cemented as required by the Rules.

The weight of the Stream Anchor Head is not less than 3/5ths the total weight of the Anchor.

Total weight of Anchor 2200 lbs.
Weight of Anchor Head 1560 lbs.

Montreal Report No. 6666 "ATALAIA"

We wish to advise that the remarks contained in Paragraphs 1 and 2 of the above are applicable in this instance also.

It might be as well to advise that Report No. 6711 on the Sister Vessel - S. S. "BARBACENA" has recently been forwarded to London, and Paragraphs 1 and 2 above, will also apply to this Vessel, also the weight of the Stream Anchor Head is not less than 3/5ths the total weight of Anchor.

Total weight of anchor 2180 lbs.
Weight of anchor head 1540 lbs.

Yours very truly,

J. S. Morrison

SURVEYOR

TSM:FC

WRECK
SECTION
No

© 2020

Lloyd's Register
Foundation

004866-204572-0229

Referred to Mr. Perris

SWP



© 2020

Lloyd's Register
Foundation