

15 MAY 1946

Lloyd's Register of Shipping.

Ship's Name "PORT DUNEDIN".

Official No. 148599.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Reconversion to open shelter deck vessel.

Tonnage opening in shelter deck refitted two frame spaces forward of original position.

Tonnage well forward bulkhead .26 plating with 3 x 3 x .38 stiffeners about 30" apart.

no end connections, 4' 6" x 48" opening (p. & s.) with 12" coamings, openings closed by portable steel plates secured with hook bolts spaced more than 12" apart.

Original forward bulkhead now becomes after bulkhead and remains intact (accommodation fitted abaft same).

Tonnage opening in shelter deck closed by efficient temporary covers.

Shelter tween deck spaces drained to machinery space by scupper pipe (p. & s.) fitted with self closing cock at lower end and overboard scupper (p. & s.) fitted with storm valve.

Overboard scupper 5" diameter (p. & s.) fitted in tonnage well with screwdown automatic non-return valve controlled from shelter deck.

Hatchways and closing appliances in second deck are in efficient condition.

Accommodation in shelter tween decks aft of tonnage well entered by steel companionway aft of tonnage opening with 5' 4" x 22" clear opening and 19" coaming, closed by 2" strong hinged wood door operated from both sides. Small steel skylight fitted (p. & s.) ~~and~~ forward of present deck house 2' 0" x 2' 0" with mean height 26" (S.S.) 23" (p.s.) with hinged steel cover secured by butterfly nuts. 18" x 15" heavy glass in skylight cover.

1 - 5" G.N. vent 36" high in starboard waterway and 2 - 5" G.N. vents 36" high in portside waterway fitted with efficient closing appliances.

1 additional portlight with strong hinged deadlight fitted in accommodation (p.s.)

W. Robinson

SURVEYOR TO LLOYD'S REGISTER.

Liv. 5/46.

Copy of above attached to Load Line Report on board vessel

Amended tonnages & closing appliances for tonnage well bulkhead openings marked on new freeboard certificate & copy. W. R.

Noted
A.H.
15.5.46



© 2020

Lloyd's Register
Foundation