

Lloyd's Register of Shipping.

Ship's Name

"PORT DUNEDIN"

Official No. 148599

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The tonnage opening has been permanently closed at this time as a wartime measure.

A small hatch has been fitted at the starboard after corner of this opening

2' - 4" x 2' - 11" x 2' - 10" above steel deck

$\frac{3}{8}$ " plating

$\frac{3}{8}$ " steel watertight cover with hinged butterfly nuts.

Note:-

As the shelter tween deck spaces are drained by overboard scuppers the freeboards are assigned from the second deck. The freeboards are unchanged but the efficiency of the tarpaulins, battening and closing arrangements of the second deck hatchways is, and must be maintained.

New Tonnage:-

9450.91 gross

5901.71 net.

NOTE:- A copy of the above has been forwarded to the Owners for attachment to the Load Line Report on board the vessel. The gross tonnage figure has not been amended on Load Line Certificate or copy (vessel sailed before figures available)

Noted
L.R.

-3 NOV 1939

W.A.F.