

"Fort Amherst" and "Fort Tamolund"

F.S.F.D.	summer mould draught =	22.01 feet ✓
C.S.S.	" " " =	18.71 "
	difference =	<u>3.30</u> "
	diff x .60 =	<u>1.98</u> ✓
		<u>18.71</u> ✓
		<u>20.69</u> ✓

It is submitted the Glasgow office be informed that with the present scantlings are not suitable for an increase in draught, but that if one web frame be fitted in No. 1 hold, two in No. 2 hold, and two in the after hold, and if intermediate frames be fitted in the tween decks in way of the forward well, where the frames are at present spaced 54 inches apart, a freeboard corresponding to a summer mould draught of 20'-8" can be attained.

S.T.B.

25-9-14