

The Scindia Steam Navigation Co.Ltd., Vizagapatam. Yard No.101.

F.E.

3m.10.47.

Sister Vessel with modifications to the "JATAKRISHNA"

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

GB

VESSEL'S NAME s.s. "JALAUHA"

REPORT Vizagapatam No. 28

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

1st Long. No. 12200

Depth "d" -

to U dk 13.11

2nd Long. No. 32900

Proportions = $\frac{L}{D}$ to B dk 10.39

Framing As approved

Sheerstrake As approved

The tank top plating increased in thickness under the hatchways
in lieu of ceiling.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed ~~100A1~~

2 Dks "pt Elec.welded"
Cell DB 343' 1149t, FPT78t, APT 46t
FK, 6 BH, Lloyd's A & CP
P 40' B 145' F 33'
O.L. 415.7'
"V"
1 15"



IT IS FURTHER SUBMITTED the Surveyor be informed it is concluded the tank top plating has been increased in thickness under the hatchways in lieu of ceiling and that the steering arrangements and windlass have been tried under working conditions and found satisfactory, but this should be confirmed.

He should be requested to state whether cement has been laid on the bottom in the double bottom under the boiler room in accordance with Section 23, Clause 1 (b) of the Rules.

If however cement has been omitted an internal annual examination of the bottom under the boiler room will be necessary. An entry to that effect will then be made in the Special Reasons List and the Surveyor should be requested to advise the Owners of this requirement.

The receipt of the ship coating and forging reports is awaited.

004900-004905-0133

Lloyd's Register
Foundation
18.12.48