

Lloyd's Register of Shipping.

Ship's Name CITY OF FLORENCE

Official No. 140559

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in APRIL, 1932.

Ash door on shell in bridge space, port only abreast fidley. Opening in shell 21" x 17" with steel angle frame all round. Hinged steel door secured by strongback.

Coal hatch on upper deck in bridge space, starboard only, abaft hatch shewn on Rpt. C.11, abreast casings. Hatch 6'0" x 4'2", 9" B.A.coaming, fitted with hatch covers (wood), cleats, battens, wedges and one tarpaulin.

Trimming hatch on upper deck in bridge space, port and starboard, abreast No.3 hatch. Hatch 2'7" x 3'6", 9" B.A.coaming. fitted with hatch covers (wood), cleats, battens, wedges, and one tarpaulin.

(W.Hpl. April, 1937).

