

9. 70951
32 Essential Independent Pumps (Identify by position)

All Good.

33 Bilge, Ballast & Oil Fuel Suction Lines, Fittings & Controls

Good.

34 Have the remaining Piping Arrangements & Fittings in the machinery space been examined as considered necessary?

Yes.

35 ~~XXXXXXXXXXXX~~

36 ~~XXXXXXXXXXXX~~

37 Heaters (state service) Feed Good.

38 ~~XXXXXXXXXXXX~~

39 ~~XXXXXXXXXXXX~~

40 ~~XXXXXXXXXXXX~~

41 Oil Fuel Tanks (Not forming part of hull structure)

Good.

42 Evaporators

Good.

43 Have Evaporator Safety Valves been tested under steam?

Yes.

44 Steering Machinery

Good.

45 Windlass

Good.

46 Fire Extinguishing Arrangements

Good.

AUXILIARY ENGINES (Identify by position)

Stbd.Inboard & Outboard Both Good.

PROPULSION

PORT

ELECTRICAL EQUIPMENT
STARBOARD

AUXILIARY EQUIPMENT

a Generators

b Exciters

c Air Coolers

d Motors

e Air Coolers

f Control Gear, Cables, etc.

g Insulation Resistance

h Insulating Oil Test

i Overspeed Governors

j Magnetic Couplings

k Air Gap

l Generators & Governors

Good.

m ~~XXXXXXXXXXXX~~

n Switchboards & Fittings

Good.

o Circuit Breakers

Good.

p Cables

Good.

q Insulation Resistance

Good.

r ~~XXXXXXXXXXXX~~

s Navigation Light Indicators

Good.

BOILERS OPENED UP & EXAMINED (Identify by position and state latest date of internal examination of each boiler)

MAIN Port 7.1.57, Centre 7.1.57, Stbd. 17.1.57 All Good.

~~XXXXXXXXXXXX~~

Superheaters All Good.

Safety Valves All Good.

Mountings, Doors & Fastenings All Good.

All Safety Valves Adjusted to Sat. 220 lbs/sq.in.
Spt. 220 lbs/sq.in.

Boiler Securing Arrangements All Good.

~~XXXXXXXXXXXX~~

~~XXXXXXXXXXXX~~

~~XXXXXXXXXXXX~~

Were Oil Burning System & Remote Controls examined working in accordance with Rules? Yes.

~~XXXXXXXXXXXX~~

Have Saturated Steam Pipes in cylindrical boiler smoke boxes been examined as required by Rules? Yes.

Funnel Good.

EXAMINATION & TESTING OF STEAM PIPES (State material)

Main Good 14.1.57(tested)

Auxiliary (over 3 in. bore)

~~XXXXXXXXXXXX~~

Have Saturated Pipes in cylindrical boiler smoke boxes been tested? Yes.

PARTICULARS OF DEFECTS & REPAIRS, ETC. (Damage repairs should be detailed separate from wear and tear repairs; state what action has been taken regarding items which are subjects of class)

Wear & tear repairs

HP main engine crosshead pins machined, bearings remetalled. All main engine piston rings renewed.

Main circulating pump steam cylinders machined, piston and rings renewed, piston valve renewed.

Impeller shaft machined, bearings renewed.

Fan engine cylinder machined, piston and rings renewed.

Sundry other minor repairs effected.

S.R.L. items (Please note difference in SRL List 149 under headings "Mount Olympus" and "City of Florence" regarding the stbd. boiler saturated S.V. chest).

The Safety valve chest was specially examined and found satisfactory. It is recommended that this item be now deleted as a condition of class and be dealt with at Owners convenience (Cat B) to be kept under observation at each Boiler Survey.

LEAVE THIS SPACE BLANK

Survey fees £ 167.10. 0

Damage fee ...

Expenses... 5. 8. 6

Stamps 9

Date when A/c rendered 29.1.57

© 2021

Lloyd's Register
Foundation