

005056-005060-0044 1/2

The condition of any item is to be described as "good" only when it ~~has been~~ examined, found or placed in good condition and is considered to be acceptable until the due

мрк 7746
19

ALSO FOR

RECEIVED
U.S. AIR MAIL
OFFICE
SEP 16 1964
TFO

SRL

POSTING

HEADER

Rpt.

(cont.)

Ship's Name SS/MS "ALVA CAPE"

Port New York

Rpt. No. 65147

6) All damaged plating in way of Starboard #1 tank (point of impact) requires to be renewed.

7) Internals in way of Main Deck Superstructure and Starboard #1 Cargo Tank to be renewed as found necessary.

8) Test specimens to be taken from designated locations.

To carry out the repairs, it is estimated that about 1500 tons of new steel will be required. The fact that all aluminum lifeboats were found completely melted will give an ample indication of the intense heat to which the structure was subjected. The main engine, auxiliary, and boilers will have to be opened up completely for examination. A fair percentage of deck and engine room piping should be renewed.

It appears from the superficial examination of the electrical equipment that all cables will require renewal, and motors and generators should be Megger tested.



© 2020

Lloyd's Register
Foundation

0044 212