

Lloyd's Register of Shipping.

Ship's Name S.S. "~~YONGE PARK~~ LAKE WINNIPEG Official No. 175575

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in July, 1944.

ALTERATIONS - Removal of D.E.M.S. Accommodation & Forward Magazine.

No. 5 'Tween Deck -

Port Side - D.E.M.S. Accommodation forward of bulkhead at Frame No.19 removed. Access door in bulkhead closed with welded plate and necessary stiffeners secured by electric welding fitted. Upper deck ventilators in way (3 - 6" dia., 1 - 10" dia. and 1 - 12" dia.) removed and 9 ship side portlights removed and openings closed with welded spigot plates.
2 sanitary scuppers, No.5 Lower hold, P.S. removed and openings closed with welded spigot plates.

Star Side - D.E.M.S. Accommodation forward of Frame No.29 removed. Original bulkhead at Frame No.33 moved aft to Frame No.29 and efficiently secured by electric welding.
One (1) - 2'-0" dia. escape hatch on upper deck and 2 - ship side portlights removed and openings closed with welded spigot plates.
Cargo battens fitted in No.5 'tween deck, P. & S. where accommodation removed.

Forward Magazine in No.1 'tween deck removed together with access trunkway, hinged steel door and 2 - 10" ventilators in way. Deck openings closed with welded plates and upper deck C.L. girder extended and bracketted to collision bulkhead.

All new work and alterations to bulkheads, upper deck and ship side satisfactorily hose tested on completion.

L.H. Beaver

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

Vancouver, B. C.

10th January, 1946.

W. Stead
J.B.D.
15/2/46

9

W

