

Nº S-52/61.-

m.v. " G E M ".-

Copy of Original.

Registry Liberian.

Tonnage:9260 gross tons.

Moored at Molasses Pier.

Veracruz, ver. M E X I C O.-

-----  
At the request of Messrs.WATSON,PHILLIPS & CIA.,  
SUCS., S.A., LLOYD'S Agents for the district of Veracruz, the  
under signed ROBERT DOBBIE, did proceed on board above mentio-  
ned vessel, on the 8th day of December 1961, at 14.30 hours, to  
inspect Port Donkey boiler and reports as follows:

SCOTCH BOILER TWO FURNACE TYPE WAS FOUND  
OPENED OUT AND CLEAN ON FIRE AND WATER  
SIDES WITH CROWNS AND COMBUSTION CHAMBER  
SCALED ON WATER SIDE AND TUBES SWEEPED OUT.  
BOILER MOUNTINGS: STOP, SAFETY, FEED CHECKS,  
STEAM TO WATER GAUGE, GAUGE COCKS, WERE  
FOUND OPENED UP AND GROUND IN AND WERE CLOSED  
UP WITH NEW PACKING.

BOILER WAS TESTED TO 180 LBS HYDRAULIC  
PRESSURE ON SAME DAY AT 1930 HOURS AND FOUND  
TIGHT.


ON THE 9TH DAY OF DECEMBER 1961 AT 1930 HOURS  
SAFETY VALVES WERE SET TO BLOW OFF AT 165 LBS.  
SAFETY VALVE SPRINGES HAD BEEN REPLACED WITH  
NEW SPRINGS.

FURNACES WERE CALIBERED AND NOTED AS PER  
ATTACHED SHEET.

-----  
This Certificate is issued without prejudice and  
subject to the terms, conditions and amount of the Insurance  
Policy.

Issued in Original and copies, one of which being  
accomplished the others to stand null and void.

Veracruz, ver. December 11th, 1961.

  
Robert Dobbie.  
(surveyor)



Lloyd's Register  
Foundation

005132-005140-021