

Lloyd's Register of Shipping.

Ship's Name

PEEBLES.

Official No. 161594

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

PARTIAL CONVERSION BACK TO ORIGINAL OPEN SHELTER DK TYPE

- ① All Tween deck scupper outside machinery space led to hold bilge now blanked off. ✓
- ② Midship scupper in Tween Dks over machy space led to machy space bilge and fitted with lever loaded cock at lower ends ✓
- ③ All intermediate Tween deck bulkheads between Tonnage Opening and Collision Bhd now fitted with Tonnage Openings P+S. and drain holes cut in bhd at side to allow drainage to midship Scupper. ✓
- ④ 5" scupper in Tonnage well P+S fitted with storm valve on shell and geared to Shelter Dk. ✓
- ⑤ The Tonnage Opening on Shelter Dk is not being opened at this time
- ⑥ The Freeboard markings have now been verified and markings for Deeper Loading (WE 41) hammered out.
- ⑦ The Freeing Port in Tonnage well P+S. remains permanently closed.

MS.

Newcastle

20.5.46.

G. Young

A.M.
13.6.46