

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) **L.H.F.D.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.	
162,350.	Hilary.	25-1931	Liverpool.

No., Date, and Port of Previous Registry (if any) -----

Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam - Single Screw.	Birkenhead.	1931	Cammell Laird & Co. Ltd., Birkenhead.

Number of Decks	2 Complete 1 partial	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ... ..	Feet.	Tenths.
Number of Masts	Two		424	2
Rigged	Schooner	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... ..	420	4
Stern	Elliptical		56	2
Build	Clencher	Main breadth to outside of plank ... ..	34	2
Galleries	None	Depth in hold from tonnage deck to ceiling at midships ...		
Head	None	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ... ..		
Framework and description of vessel	Steel Passgr. & Cargo	Depth from top of beam amidships to top of keel ... ..	38	1
Number of Bulkheads	Nine	Depth from top of deck at side amidships to bottom of keel	37	2
Number of water ballast tanks, and their capacity in tons	8- 994 tons.	Round of beam ... ..	1	0
		Length of engine room, if any ... ..	78	7

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	13430 Tons.	Ditto per inch immersion at same depth	45.25 Tons.
----------------------------------------------------------------------------------	-------------	----------------------------------------	-------------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Triple Expansion with Exhaust Turbine Installation	Engines. British	Engines. 1931	Engines. and	3 29"	57"		678 5200
No. of Shafts.	Particulars of Boilers. Description: Cylindrical Number: 5 Iron or Steel: Steel Loaded Pressure: 230 lbs. □	Boilers. British	Boilers 1931	Boilers. Cammell Laird and Co., Ltd., Birkenhead.	48 1/2" & 81 1/2"			14 1/4 knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ... ..	6183.57	On account of space required for propelling power	2368.83
Space or spaces between Decks ... ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	529.89
Turret or Trunk ... ..	189.63		
Forecastle ... ..			
Bridge space ... ..		These spaces are the following, viz.:— Tween decks, Forecastle and (Number of Seamen or Apprentices for whom accommodation is certified... 130.....)	
Poop or Break ... ..		Round Houses	
Side Houses ... ..			
Deck Houses ... ..	1012.87		
Chart House ... ..	6.87		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ... ..		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ... ..	9.66	Master's Accmdn. 16.35 Chart Space 6.87 Wireless Tel. Space 4.88 B's'n's Store 71.48 Water Ballast Spaces 54.08 Total ... ..	153.66 3052.38
Gross Tonnage ... ..	7402.60	Cubic Metres	
Deductions, as per Contra ... ..	3052.38	20949.36 8638.24	
Register Tonnage ... ..	4350.22	12311.12	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 1152.37 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 149.51 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space at after end of Round House on Promenade Deck.

L- 7.9 ft - 21.84 tons.

Name of Master	Wesson Cecil Herbert Jones	Certificate of { Service No. 035678 Competency No.
----------------	----------------------------	-------------------------------------------------------

No. of Owners  
Name, Residence, and Description of Managing Owner if there are more owners than one.

The Booth Steamship Company  
Limited,  
Cunard Building,  
Liverpool.  
Sixty-four Shares.  
Dated 2nd July, 1931.

Jasper Moon  
of Cunard Building,  
Liverpool  
-Manager-

© 2021

Lloyd's Register  
Foundation