

COPY.

H

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

5th August, 1940.

Dear Sir,

S.S. "LARISTAN" - No.78121 in the Register Book

M.

I have to confirm the conversation on the telephone on the 3rd instant regarding the owners' proposal to fit a Marconi crystal type echometer, type F4, TER projector, in the after cofferdam between the cargo tanks and oil fuel bunkers in the above vessel, and to say that this could be done, provided the following requirements of the Committee were complied with:-

1. Fitting is to be in accordance with standard approved plan.
2. Electrical connections are to be in accordance with Section 15 of the Rules for Electrical Equipment.
3. Cables in the cofferdam are to be enclosed in heavy gauge screwed gas-tight tubing and the converter boxes are to be of approved gas-tight pattern.
4. The fittings are to be of flame-proof construction.


It will be observed that the wording of the above requirements differs slightly from that given in your letter to ~~the~~ Messrs. Barclay, Curle & Co., a copy of which was forwarded with your letter of the 3rd instant.

I am, Dear Sir,

Yours faithfully,

The Secretary,

GLASGOW.



© 2021

Lloyd's Register  
Foundation  
Secretary.

005311-005317-0017