

Port of - Glasgow -GLASGOW REPORT No 628149<sup>th</sup> July 1940

## REPORT ON MASTS, SPARS, AND RIGGING.

Sir

Having, in accordance with your instructions,  
examined the Masts, Spars, Iron Work of same, and Rigging, of the  
(Name of Vessel) C.T. Laristan.

on the (Date of examination) 8<sup>th</sup> July 1940,

I have to report that I found The Ironwork and Attachments to Fore and  
Main Mast's under Hammer Test in good Condition. The wood top masts  
Pricket and Hammer Tested. (The Mast coat Canvas covers to be Renewed)

- Rigging -

- all - Stays & Shrouds to Fore & Main Masts the serving at Bottom of Wire to be  
Removed the wire cleaned & Re-served (Note any defective wire to be Renewed.
- all - setting up screws and shackles to be made workable. (Note any  
defective screws or shackles to be Renewed.)

- Main funnel -

- all - Guys to Main funnel - The connections for shackles to be Examined  
Top & Bottom, and setting up screws made workable.

Fee £ : :

To the Surveyors,  
Lloyd's Register of Shipping,

James CameronRepaired effectedGeorge Sutherland24<sup>th</sup> August 1940.