

15 JUL 1952

NEWCASTLE-ON-TYNE, No F.994.

32407

Rpt. C. 11 (Contd.)

Index No. ....

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name SAN CASTO Official No. 149989

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Nos 1, 4 and 5 Wing tanks p.v.S.

6 steel W.T. Hatches fitted over existing upper deck openings at after end of each tank. Opening in deck 2'-0" x 2'-0".

Hatches 2'-6" x 2'-6". Coaming 2'-6" high x 40".

60" steel hinged cover fitted with packing and 4 Joggles.

Nos 2/3 Wing Tank p.v.S.

(Nos W.B. Tanks)

Deck openings reduced to 2'-0" x 18" manhole with bolted plate cover.

Air Pipes

2" Air pipe led from each wing tank hatch coaming into 4" main.

Storm Valve Discharges

Additional S.V. Discharges fitted amidships 1-2 1/2", aft 1-4", 6-2 1/2" and 1-2". All to Rule Regmt.

S.V. Discharges from Toile Space have been dispensed with.

Ventilators

2 - 9" Vents and 6 - 6" Vents on fore-castle deck have been dispensed with.

A copy of this has been placed on board.

J Ballantine

18/6/52.

SURVEYOR TO LLOYD'S REGISTER.  
NEWCASTLE-ON-TYNE.

*[Handwritten signature]*



© 2020

Lloyd's Register Foundation